

**MEMBRANE ROOF REPLACEMENT FOR  
ENO MEMORIAL HALL and BELDEN TOWN OFFICES**

**1404  
SIMSBURY, CT**

**ADDENDUM NUMBER ONE**

**30 July 2014**

**MODIFICATIONS TO THE SPECIFICATIONS**

SECTION 00010, PARAGRAPH 5: REVISE TO READ:

“... July 29, 2014. Attendance, although not mandatory, is strongly encouraged. All Bidders shall comply with the requirements of Article 2 of “Instructions to Bidders”.

SECTION 01500, PARAGRAPH 1.04: REVISE TO READ:

Field office will not be required for this project.

SECTION 01500: ADD:

- 1.09 Work Hours: Construction activities will commence no earlier than 7:00 a.m. and cease no later than 5:00 p.m.. Buildings are open to the public from 8:30 a.m. to 7:00 p.m.

SECTION 07600: ADD:

- 3.04 Replacement: Where documents call for replacement of existing counterflashing the following procedures shall be followed:
- a. Remove completed existing flashing.
  - b. Clean reglet of all caulking.
  - c. Install new lead-coated counterflash with hemmed edges using lead wedges.
  - d. Caulk weather-tight using Pecora AC-20 or equal.

\* \* \* \*