

Stormwater Management Report

Vessel Multi-Family Development

446 Hopmeadow Street
Simsbury, CT 06089

December 16, 2022

Prepared for:
Vessel Technologies, Inc.
46 West 55th Street
New York, NY 10019

Prepared by:
H+H Engineering Associates, LLC
232 Greenmanville Avenue
Suite 201
Mystic, CT 06355

H+H
ENGINEERING
ASSOCIATES




Table of Contents

	Page
1. INTRODUCTION	3
2. PURPOSE OF REPORT	3
3. BASIS OF DESIGN	6
4. HYDROLOGIC AND HYDRAULIC METHODS	6
5. STORMWATER MANAGEMENT	7
5.1 Existing Condition Drainage Areas and Analysis Points	7
5.2 Proposed Condition Drainage Areas	7
5.3 Proposed Condition Stormwater Management BMPs	8
5.4 Storm Drain System Outlet Locations	9
6. SOURCE CONTROL AND POLLUTION PREVENTION MAINTENANCE AND OPERATION	13
7. CONCLUSION	15

FIGURES

FIGURE 1 – SITE LOCATION MAP

FIGURE 2 – FIRMETTE MAP

FIGURE 3 – PRE-DEVELOPMENT DRAINAGE AREA MAP

FIGURE 4 – POST-DEVELOPMENT DRAINAGE AREA MAP

FIGURE 5 – STORMWATER RUNOFF SUMMARY

FIGURE 6 – STAGE-STORAGE SUMMARIES

TECHNICAL APPENDIX

APPENDIX A – WATER QUALITY VOLUME AND WATER QUALITY FLOW CALCULATIONS

APPENDIX B – RIPRAP APRON DESIGN

APPENDIX C – PRE-DEVELOPMENT HYDROCAD REPORT

APPENDIX D – POST-DEVELOPMENT HYDROCAD REPORT

1. INTRODUCTION

The project is located at 446 Hopmeadow Street (U.S. Route 202/CT Route 10) in Simsbury, Connecticut (hereinafter referred to as the "Site") and is identified as Lot N003C on Tax Assessor's Map G13, Block 142. The Site is located on the east side of Hopmeadow Street, approximately 200 feet north of the intersection of Hopmeadow Street and Powder Forest Drive. The Site is 1.96 acres with 149.9 linear feet of frontage along Hopmeadow Street and is currently developed as a single-family residence (see Figure 1 – Site Location Map). The Site is located in the High Density Residential 'R-15' Zoning District. Adjacent properties are located in the High Density Residential 'R-15' Zone, the Low Density Residential 'R-40' Zone, the Planned Area Development 'PAD' Zone, and the Designed Multiple Residence 'RD' Zone. Existing topography on site is moderate with contours ranging from elevation 102 along the southern property line, to elevation 84 along the northern property line. Per NRCS soil mapping, the underlying soil consists of Hinckley loamy sand (Hydrologic Group A). The Site is not located within a FEMA Flood Hazard Zone (see Figure 2 – Firmette Map).


The proposed development consists of the construction of a new four-story 14,063 square-foot multi-family residential building, consisting of 77 one-bedroom units (575 square-feet) and 3 two-bedroom units (1,048 square-feet). Site improvements will include a new two-way access drive from Hopmeadow Street, a new 94 vehicle parking lot, new sanitary sewer, water, and electrical service connections, new landscaping improvements, and a new stormwater management system.

This report presents the basis of the project hydrologic and hydraulic analysis of the site, the design for the new site drainage systems, and Best Management Practices (BMPs) incorporated into the site design to manage and treat stormwater runoff in accordance with the 2004 CT DEEP Stormwater Quality Manual (SQM) and the Town of Simsbury Zoning Regulations.

2. PURPOSE OF REPORT

This report presents the basis of design for stormwater management including drainage and stormwater treatment. The report demonstrates that the development:

- Does not increase peak rates of runoff from watersheds encompassing the new buildings and parking areas.
- Does not degrade the quality of receiving groundwater, waterbodies, or watercourses.
- Complies with the 2004 CT DEEP SQM and the Town of Simsbury Stormwater Management Standards to the greatest extent practicable.



PROJECT NO. 2022-0013	SCALE: 1"=1,000'
DRAWN BY: SMM	DATE: 12/16/2022
CHECKED BY: SMM	DATE: 12/16/2022
SHEET NUMBER: 1 OF 1	
DRAWING: FIGURE 1	

**STORMWATER REPORT -
SITE LOCATION MAP**

VESSEL MULTI-FAMILY HOUSING
446 HOPMEADOW STREET, SIMSBURY, CT 06089

VESSEL TECHNOLOGIES, INC.
46 WEST 55TH STREET, NEW YORK, NY 10019

HHH
ENGINEERING
ASSOCIATES

232 Greenmanville Avenue
Suite 201
Mystic, CT 06355
860-980-8008 (O); 413-579-4488 (M)
www.hh-engineers.com

National Flood Hazard Layer FIRMette

72°49'2"W 41°51'32"N



Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS

- Without Base Flood Elevation (BFE)
Zone A, V, A99
- With BFE or Depth *Zone AE, AO, AH, VE, AR*
- Regulatory Floodway

0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile *Zone X*

- Future Conditions 1% Annual Chance Flood Hazard *Zone X*
- Area with Reduced Flood Risk due to Levee. See Notes. *Zone X*
- Area with Flood Risk due to Levee *Zone D*

OTHER AREAS OF FLOOD HAZARD

- NO SCREEN *Zone X*
- Area of Minimal Flood Hazard *Zone X*
- Effective LOMRs *Zone D*
- Area of Undetermined Flood Hazard *Zone D*

OTHER AREAS

- Channel, Culvert, or Storm Sewer
- Levee, Dike, or Floodwall

GENERAL STRUCTURES

- Cross Sections with 1% Annual Chance Water Surface Elevation
- Coastal Transect
- Base Flood Elevation Line (BFE)
- Limit of Study
- Jurisdiction Boundary
- Coastal Transect Baseline
- Profile Baseline
- Hydrographic Feature

OTHER FEATURES

- Digital Data Available
- No Digital Data Available
- Unmapped

MAP PANELS

The pin displayed on the map is an approximate point selected by the user and does not represent an authoritative property location.

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards.

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on **8/22/2022 at 1:44 PM** and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.

This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.



72°48'24"W 41°51'16"N

Feet 1:6,000

0 250 500 1,000 1,500 2,000

Basemap: USGS National Map; Orthoimagery: Data refreshed October, 2020

3. BASIS OF DESIGN

The layout, grading and drainage design for the project are shown on the Site Development Plans. The basis of the grading and drainage design is as follows:

1. Rainfall data is from the National Weather Service NOAA Atlas 14, Volume 10, Version 3.
2. Drainage systems are designed to meet or exceed the water quality and peak rate of runoff goals established in the CT DEEP SQM.
3. Stormwater treatment Best Management Practices (BMPs) are designed to remove pollutants, such as nutrients, solids, metals, pathogens, pesticides, and hydrocarbons from stormwater runoff and to reduce temperatures of runoff from paved surfaces during hot weather.
4. Pretreatment of runoff for the removal of sediments, oil and grease will be accomplished using deep sump catch basins and outlet hoods.
5. BMPs for this project include an underground infiltration system with isolator rows designed to infiltrate the runoff generated from the proposed parking lot, a bioretention basin designed to treat and infiltrate the runoff generated from the building rooftop, and two separate drywells/basins designed to capture and infiltrate off-site runoff entering the Site.

4. HYDROLOGIC AND HYDRAULIC METHODS

The methods described in Urban Hydrology for Small Watersheds, 2nd Edition, (Technical Release Number 55 [TR-55]) from the Natural Resources Conservation Service (formerly the Soil Conservation Service – [SCS], 1986) were used to calculate stormwater peak-flow generated from pre- and post-development conditions. These methods, which are incorporated into the HydroCAD computer software program, use well documented procedures to calculate stormwater runoff volume, peak-flow rate of discharge, hydrographs and storage volumes required for floodwater reservoirs in small watersheds. The method uses the SCS Runoff Curve Number method to estimate runoff volume, calculate times of concentration, produce tabular hydrographs, and estimate basin storage capacity. Output data from all computer analysis and design are provided in the Technical Appendix.

This report presents the basis of the hydrologic and hydraulic analysis and design of the stormwater management including drainage and stormwater treatment systems completed in accordance with the Connecticut Department of Transportation Drainage Manual (Drainage Manual). The report also presents a Stormwater Management Plan prepared in accordance, to the greatest extent practical, with the 2004 CT DEEP SQM. Times of concentration applicable to the pre- and post-development were developed using the NRCS-velocity method. A minimum time of concentration of 5 minutes was used for paved surfaces and 10 minutes for vegetated areas.

5. STORMWATER MANAGEMENT

The existing site is developed as a single-family residence and includes buildings, a paved driveway, walkways, and lawn and wooded areas. Site improvements will increase impervious areas, resulting in rate and volume increases of stormwater runoff from the Site. Hydrologic analyses of pre- and post-development conditions were completed to assess these increases and to design mitigation measures for water quality and to reduce post-development discharges.

5.1 Existing Condition Drainage Areas and Analysis Points

The existing drainage pattern for the site in the vicinity of the proposed improvements is characterized by one drainage area that drains to the north toward Second Brook and the associated wetland, as shown on Figure 3 – Pre-Development Drainage Area Map, and described as follows:

- **DA1:** Approximately 4.67 acres of land, currently developed as multiple single-family residences, and includes 2.48 acres of lawn, 1.78 acres of woods, 0.39 acres of impervious surfaces (rooftops, pavement), and 0.02 acres of gravel.
- **Drainage Analysis Point 1:** The drainage analysis point is the southern edge of the off-site wetland to the north of the Site.

5.2 Proposed Condition Drainage Areas

The proposed development results in the modification of the drainage areas along with changes in impervious coverage (building rooftop, pavement surfaces and concrete surfaces). These conditions are shown on Figure 4 – Post-Development Drainage Area Map, and described as follows:

- **DA1:** For analysis purposes, the proposed condition DA1 was subdivided into 2 subareas.
 - **DA1A:** Approximately 1.37 acres of land, located mostly offsite, consisting of 0.67 acres of lawn, 0.55 acres of woods and 0.15 acres of impervious surfaces that drain to Stormwater Management Area C (drywell and basin).
 - **DA1B:** Approximately 0.31 acres of land, located mostly offsite, consisting of 0.20 acres of lawn, 0.06 acres of woods and 0.0514 acres of impervious surfaces that is captured on site by a new curtain and directed to Stormwater Management Area C.
- **DA2:** For analysis purposes, the proposed condition DA2 was subdivided into 2 subareas.
 - **DA2A:** Approximately 0.32 acres of new building rooftop that is directed to Stormwater Management Area B (bioretention basin).
 - **DA2B:** Approximately 0.29 acres of land, located partially offsite, consisting of 0.25 acres of lawn, and 0.04 of wood that drains to Stormwater Management Area B,

- **DA3:** Approximately 0.32 acres of land, located mostly offsite and along Hopmeadow Street, consisting of 0.16 acres of lawn, 0.13 acres of woods, and 0.03 acres of impervious surfaces that drain to Stormwater Management Area D (drywell and basin).
- **DA4:** Approximately 0.97 acres of land consisting of 0.84 acres of new pavement and walkways, and 0.13 acres of lawn that drain to Stormwater Management Area A (ADS Stormtech SC-3500).
- **DA5:** Approximately 1.09 acres of land north and east of the proposed improvements consisting of 0.43 acres of lawn, 0.64 acres of woods and 0.02 acres of impervious surfaces that drain to the wetland.

Modeling results for the existing and proposed conditions drainage areas are provided in Figure 5 – Stormwater Runoff Summary, and the hydrologic and hydraulic modeling parameters are provided in the HydroCAD printouts (Technical Appendix).

5.3 Proposed Condition Stormwater Management BMPs

For the post-development conditions, the intent of the proposed stormwater management improvements is to route stormwater runoff from new impervious surfaces through the proposed stormwater BMPs to provide water quality treatment, peak rate reduction, and promote groundwater recharge through infiltration. Additionally, runoff generated off-site that crosses onto the Site will be captured and infiltrated. Four separate Stormwater Management Areas are included in the design and are described below:

- **Stormwater Management Area A:** ADS Stormtech MC-3500 Underground Infiltration/Detention System with Isolator Rows – Catch basins within the parking lot direct the runoff from the parking area and roof (DA4) into the proposed ADS Stormtech MC-3500 infiltration/detention system, which will retain, attenuate and infiltrate stormwater runoff from the impervious areas and treat stormwater runoff through filtration using two isolator rows that are sized to treat in excess of the Water Quality Flow (WQF) and infiltrate through the 2-year storm event. The flow is directed into two separate Isolator Rows, which are a row of chambers wrapped in filter fabric which allow for sediment settling as stormwater fills the chamber and flows through the filter fabric and into the other chambers. The retained water in these chambers is then infiltrated back into the ground. Overflow from the chambers is directed to an outlet pipe and riprap apron located to the north.
- **Stormwater Management Area B:** Bioretention Basin – The stormwater runoff generated from the proposed building rooftop (DA2A) and a portion of the off-site runoff (DA2B) will be collected and discharged into the proposed Bioretention Basin which will retain, attenuate, and infiltrate stormwater runoff and treat stormwater runoff through plant filtration and infiltration. The Bioretention Basin is designed to infiltrate through the 25-year storm event. Overflow from the basin is directed to an outlet pipe and riprap apron located to the north. An overflow spillway is proposed to direct runoff toward the

catchment system located in Hopmeadow Street in case of emergency. The bioretention basin plantings are native and have been designed by a Landscape Architect.

- **Stormwater Management Area C:** Drywell and Collection Basin – Off-site stormwater runoff generated from the properties to the south continue onto the Site. A portion of this runoff (DA1A) is collected by a shallow detention basin surrounding a 6'(dia.) x 2'(h) concrete drywell which is designed to infiltrate stormwater runoff. The detention basin also provides stormwater storage capacity for larger storm events. The remaining stormwater runoff entering the Site (DA1B) is collected by a curtain drain with a 6" underdrain prior to reaching the proposed parking lot and is redirected to the concrete drywell. The Drywell and Collection Basin is designed to infiltrate through the 100-year storm event. An overflow spillway is proposed to direct runoff away from the building in case of emergency.
- **Stormwater Management Area D:** Drywell and Collection Basin – Off-site stormwater runoff generated from the properties to the south (DA3) continue onto the Site. This runoff is collected by a shallow detention basin surrounding a 6'(dia.) x 4'(h) concrete drywell which is designed to infiltrate stormwater runoff. The detention basin also provides stormwater storage capacity for larger storm events. The Drywell and Collection Basin is designed to infiltrate through the 100-year storm event. An overflow spillway is proposed to direct runoff toward the catchment system located in Hopmeadow Street in case of emergency.

The Water Quality Volume & Water Quality Flow Calculations for Stormwater Management Areas A and B are included in the Technical Appendix. A summary of the stage and storage volume for Stormwater Management Areas A, B, C and D is included in Figure 6 – Stage-Storage Summaries.

5.4 Storm Drain System Outlet Locations

Stormwater Management Area A – Outflow from the ADS Stormtech MC-3500 system is directed through an outlet control structure and 12" HDPE pipe to a wooded area to the north which then sheetflows to the off-site inland wetland.


Stormwater Management Area B – Overflow from the bioretention pond is directed through an outlet control structure and 12" HDPE pipe to a wooded area to the north which then sheetflows to the off-site inland wetland. Emergency overflow is directed through a riprap spillway located on the eastern slope of the basin and directs flow to the east, away from the proposed building.

Stormwater Management Area C – Emergency overflow from the drywell and collection basin is directed through a riprap spillway located on the northern slope of the basin and directs flow toward Stormwater Management Area A.

Stormwater Management Area D – Emergency overflow from the drywell and collection basin is directed through a riprap spillway located on the western slope of the basin and directs flow toward the catchment system in Hopmeadow Street.

PEAK RATE OF RUNOFF (CFS) SUMMARY			
STORM FREQUENCY	ANALYSIS POINT - EDGE OF WETLAND		
	EXISTING	PROPOSED	CHANGE
WQV	0.00	0.00	NO CHANGE
2-YEAR	0.01	0.00	-0.01
10-YEAR	0.50	0.47	-0.03
25-YEAR	1.61	1.46	-0.15
100-YEAR	4.45	4.22	-0.23

RUNOFF VOLUME (CF) SUMMARY			
STORM FREQUENCY	ANALYSIS POINT - EDGE OF WETLAND		
	EXISTING	PROPOSED	CHANGE
WQV	0	0	NO CHANGE
2-YEAR	223	0	-223
10-YEAR	6,149	1,999	-4,150
25-YEAR	13,040	4,644	-8,396
100-YEAR	27,291	12,013	-15,278

PROJECT NO. 2022-0013	SCALE: N.T.S.	STORMWATER REPORT - STORMWATER RUNOFF SUMMARY VESSEL MULTI-FAMILY HOUSING 446 HOPMEADOW STREET, SIMSBURY, CT 06089 VESSEL TECHNOLOGIES, INC. 46 WEST 55TH STREET, NEW YORK, NY 10019	 232 Greenmanville Avenue Suite 201 Mystic, CT 06355 860-980-8008 (O); 413-579-4488 (M) www.hh-engineers.com
DRAWN BY: SMM	DATE: 12/16/2022		
CHECKED BY: SMM	DATE: 12/16/2022		
SHEET NUMBER: 1 OF 1			
DRAWING: FIGURE 5			

**STORMWATER MANAGEMENT AREA 'A'
ADS STORMTECH SC-3500 INFILTRATION SYSTEM**

STORM FREQUENCY	WATER SURFACE ELEVATION (FT.)	STORAGE VOLUME (CF)
WQV	84.72	14
2 YEAR	85.95	1,258
10 YEAR	87.41	3,298
25 YEAR	88.23	4,298
100 YEAR	89.19	5,196

ADS STORMTECH SC-3500 INFILTRATION SYSTEM ELEVATIONS:

TOP OF STONE ELEV. = 90.20
TOP OF CHAMBER ELEV. = 89.20
BOTTOM OF CHAMBER ELEV. = 85.45
BOTTOM OF STONE ELEV. = 84.70

OUTLET CONTROL STRUCTURE ELEVATIONS:
TOP OF FRAME (MANHOLE COVER) ELEV. = 93.60
RECTANGULAR WEIR INV. ELEV. = 89.00
4"x12" UPPER ORIFICE = 87.80
4" DIA. LOW-FLOW ORIFICE = 86.00
12" INV. OUT ELEV. = 84.70

EXFILTRATION RATE = 20.0 IN/HR

**STORMWATER MANAGEMENT AREA 'B'
BIORETENTION BASIN**

STORM FREQUENCY	WATER SURFACE ELEVATION (FT.)	STORAGE VOLUME (CF)
WQV	91.24	267
2 YEAR	92.11	1,521
10 YEAR	92.83	2,933
25 YEAR	93.28	4,015
100 YEAR	93.50	4,576


BIORETENTION BASIN ELEVATIONS:

TOP OF BERM ELEV. = 94.10
TOP OF SPILLWAY ELEV. = 93.60
BOTTOM OF BASIN ELEV. = 91.00

OUTLET CONTROL STRUCTURE ELEVATIONS:

TOP OF FRAME (CB GRATE) ELEV. = 93.40
12" INV. OUT ELEV. = 90.00

EXFILTRATION RATE = 2.0 IN/HR

PROJECT NO. 2022-0013	SCALE: N.T.S.	STORMWATER REPORT - STORMWATER TREATMENT PRACTICES STAGE-STORAGE SUMMARIES VESSEL MULTI-FAMILY HOUSING 446 HOPMEADOW STREET, SIMSBURY, CT 06089 VESSEL TECHNOLOGIES, INC. 46 WEST 55TH STREET, NEW YORK, NY 10019	 HHH ENGINEERING ASSOCIATES 232 Greenmanville Avenue Suite 201 Mystic, CT 06355 860-980-8008 (O); 413-579-4488 (M) www.hh-engineers.com
DRAWN BY: SMM	DATE: 12/16/2022		
CHECKED BY: SMM	DATE: 12/16/2022		
SHEET NUMBER: 1 OF 2			
DRAWING: FIGURE 6			

**STORMWATER MANAGEMENT AREA 'C'
DRYWELL AND COLLECTION BASIN**

STORM FREQUENCY	WATER SURFACE ELEVATION (FT.)	STORAGE VOLUME (CF)
WQV	89.10	0
2 YEAR	89.12	1
10 YEAR	93.41	253
25 YEAR	93.76	548
100 YEAR	94.29	1,656

DRYWELL ELEVATIONS:
 TOP OF FRAME (CB GRATE) ELEV. = 93.00
 6" INV. IN (FROM CURTAIN DRAIN) = 91.70
 BOTTOM OF DRYWELL ELEV. = 90.10
 BOTTOM OF STONE ELEV. = 89.10

COLLECTION BASIN ELEVATIONS:
 TOP OF BERM ELEV. = 94.80
 TOP OF SPILLWAY ELEV. = 94.30
 BOTTOM OF BASIN ELEV. = 93.00

EXFILTRATION RATE = 20.0 IN/HR

**STORMWATER MANAGEMENT AREA 'D'
DRYWELL AND COLLECTION BASIN**

STORM FREQUENCY	WATER SURFACE ELEVATION (FT.)	STORAGE VOLUME (CF)
WQV	91.50	0
2 YEAR	91.50	0
10 YEAR	92.40	33
25 YEAR	97.83	251
100 YEAR	98.51	393

DRYWELL ELEVATIONS:
 TOP OF FRAME (CB GRATE) ELEV. = 97.40
 BOTTOM OF DRYWELL ELEV. = 92.50
 BOTTOM OF STONE ELEV. = 91.50

COLLECTION BASIN ELEVATIONS:
 TOP OF BERM ELEV. = 100.10
 TOP OF SPILLWAY ELEV. = 99.60
 BOTTOM OF BASIN ELEV. = 97.40

EXFILTRATION RATE = 20.0 IN/HR

PROJECT NO. 2022-0013	SCALE: N.T.S.
DRAWN BY: SMM	DATE: 12/16/2022
CHECKED BY: SMM	DATE: 12/16/2022
SHEET NUMBER: 2 OF 2	
DRAWING: FIGURE 2	

**STORMWATER REPORT -
STORMWATER TREATMENT PRACTICES
STAGE-STORAGE SUMMARIES**

VESSEL MULTI-FAMILY HOUSING
 446 HOPMEADOW STREET, SIMSBURY, CT 06089

VESSEL TECHNOLOGIES, INC.
 46 WEST 55TH STREET, NEW YORK, NY 10019

**HHH
ENGINEERING
ASSOCIATES**

232 Greenmanville Avenue
 Suite 201
 Mystic, CT 06355
 860-980-8008 (O); 413-579-4488 (M)
 www.hh-engineers.com

6. SOURCE CONTROL AND POLLUTION PREVENTION MAINTENANCE AND OPERATION

Source control and pollution prevention practices for this project are intended to eliminate the generation of pollutants at their source, reduce the types and concentration of pollutants in stormwater runoff and to assure that the BMPs continue to function to remove oil and grease and TSS. The site property managers will be responsible for maintaining the stormwater management system and the goal of this section is to inform managers about system operations.

The following maintenance and operation measures are recommended for source control.

Parking Lots

The access drive and parking areas shall be swept once per year, preferably after the end of the winter sanding season.

Landscaping

Normal landscaping maintenance shall consist of pruning, mulching, planting, mowing lawns, raking leaves, etc. Use of fertilizers and pesticides will be controlled and limited to minimal amounts necessary for healthy landscape maintenance.

Trees will be fertilized no more than once in the spring with an organic fertilizer. Shrubs and lawn will be fertilized with an organic slow-release fertilizer each spring. Liming of lawn areas to control pH will also be done in the spring if soil testing indicates that it is necessary.

Pesticides will only be used as a control method when a problem has been clearly identified and other natural control methods are not successful. All pesticide applications shall be by licensed applicators, where necessary.

Trash Collection

Trash receptacles service the facility, and dumpsters exist on-site. The pickup of trash will occur on a regular basis and all trash will be disposed of legally off-site.

Outdoor Storage

There will be no outdoor storage of hazardous chemicals, fertilizer, pesticides, or herbicides anywhere on site.

Snow Removal & Storage

Snow shall be shoveled and plowed from sidewalk and parking areas as soon as practical during and after winter storms and deposited in snow storage areas on the site or removed.

Catch Basins and Manholes

A Connecticut-Licensed hauler shall pump the sumps of onsite catch basins and manholes and shall dispose of the sand legally. Road sand may be reused for winter sanding but may not be

stored on-site. As part of the hauling contract, the hauler shall notify the property owner in writing where the material is being disposed.

For the first three years each catch basin and manhole shall be inspected every four months, with one inspection occurring during the month of April. Any debris occurring within one foot from the bottom of each sump shall be removed by Vacuum "Vactor" type of maintenance equipment. After the first three years the inspection schedule may be adjusted to meet actual operating conditions, however, one inspection shall always be conducted in April.

Stormtech underground infiltration systems and Isolator Rows

The Isolator rows shall be cleaned at the end of construction once the contributing areas are fully stabilized. For the first year of operation following construction, the chamber rows shall be inspected once every 6 months.

After the first year of operation, the chambers shall be inspected a minimum of once per year. If upon visual inspection it is found that sediment has accumulated, a stadia rod should be inserted to determine the depth of the sediment. When the average depth of accumulation exceeds 3", a clean-out should be performed and properly disposed off-site. Clean-out should be accomplished using a Jetvac process.

A detailed maintenance logbook shall be kept on-site for the units by the property owner/manager. Information is to include, but not be limited to, the date of inspection, record of sediment depth, general observations, and date of cleaning performed.

Maintenance of all Stormtech systems should follow all manufacturers' recommendations.

Bioretention Basin

The bioretention basin shall be inspected every six months and/or after storm events of 2 inches of rainfall or greater. Inspections shall include the following:

- Inspect filter media standing water or other evidence of clogging.
- Check for sediment accumulation, trash, and debris.
- Check for blockages, structural integrity, and evidence of erosion at inlets, outlets, and overflow spillways.

Regular maintenance includes the following:

- Prune trees and shrubs as needed.
- Basin floor/side slopes shall be mowed 6" to 8" as needed. grass clippings, leaves and accumulated sediment and debris shall be removed during the summer; however, plant matter shall be left in place over winter months to insulate the soil and add organic matter to the soil. removal criteria shall include when plant matter is smothering or killing vegetation and aesthetics.
- Remove sediment greater than 1.0 inch deep in March-April in the filter media bed in a manner to minimize damage to vegetation.
- Inspect soil and repair eroded areas seasonally or as necessary.

- Remove any invasive species (including roots) that have become established within the basin and embankments.
- If there is an accumulation of organic debris or sediment on the floor of the basin, or if ponded water is regularly observed more than 48 hours after a rainfall event, the top 6" shall be removed and the exposed soil surface rototilled to a depth of 12". Sedimentation should be removed when it is visibly dry and readily separates from the basin floor to minimize smearing. After this work has been done, the bottom of the basin shall be restored to its original condition.
- No pesticides or non-organic fertilizers shall be used in areas draining to the bioretention basin.

Drywells and Collection Basins

The drywells shall be cleaned at the end of construction once the contributing areas are fully stabilized. For the first year of operation following construction, the drywells shall be inspected once every 6 months.

After the first year of operation, the drywells shall be inspected a minimum of once per year. If upon visual inspection it is found that sediment has accumulated, a stadia rod should be inserted to determine the depth of the sediment. When the average depth of accumulation exceeds 3", a clean-out should be performed and properly disposed off-site. Clean-out should be accomplished using a Jetvac process.

Collection Basins shall be routinely checked for sediment accumulation, trash, and debris. Basin shall be mowed to 4-6" as needed. Grass clippings, leaves and accumulated sediment and debris shall be removed. Remove any invasive species (including roots) that have become established within the basin and embankments.

A detailed maintenance logbook shall be kept on-site for the units by the property owner/manager. information is to include, but not be limited to, the date of inspection, record of sediment depth, general observations, and date of cleaning performed.

7. CONCLUSION

The new stormwater management improvements were designed in accordance with the 2004 CT DEEP SQM and Simsbury regulations. BMPs were incorporated in the site design that attenuate post-development runoff rates, treat in excess of the WQV/WQF and infiltrate in excess of the WQV and GRV from the development. Overall, the stormwater management system provides quantitative and qualitative improvements for the site.


Technical Appendices for Stormwater Management Report

Vessel Multi-Family Development
446 Hopmeadow Street
Simsbury, CT 06089

December 16, 2022

Prepared for:
Vessel Technologies, Inc.
46 West 55th Street
New York, NY 10019

Prepared by:
H+H Engineering Associates, LLC
232 Greenmanville Avenue
Suite 201
Mystic, CT 06355



**Appendix A –
Water Quality Volume
and Water Quality Flow
Calculations**

WQV & WQF CALCULATIONS - STORMWATER MANAGEMENT AREA 'A'

Project: 446 Hopmeadow Street, Simsbury	Calculated By	Date
Client: Vessel Technologies, Inc.	SMM	12/14/2022

Water Quality Volume (WQV)

0.97 ac	A = Area draining to the practice
0.84 ac	A_i = Impervious area draining to the practice
0.87 decimal	I = Percent impervious area draining to the practice, in decimal form
0.83 unitless	R_v = Runoff coefficient = $0.05 + (0.9 \times I)$
0.81 ac-in	$WQV = 1" \times R_v \times A$
2,934 cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")


Water Quality Flow (WQF)

1.00 inches	P = amount of rainfall.
0.83 inches	Q = Water Quality Depth. $Q = WQV / A$
98 unitless	CN = unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 \cdot [Q^2 + 1.25 \cdot Q \cdot P]^{0.5})$
0.2 inches	S = potential maximum retention. $S = (1000 / CN) - 10$
0.032 inches	I_a = initial abstraction. $I_a = 0.2S$
10.0 minutes	T_c = Time of Concentration
590.0 cfs/mi ² /in	q_u is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
0.745 cfs	$WQF = q_u \times WQV$. Conversion: to convert "cfs/mi ² /in" * ac-in" to "cfs" multiply by 1mi ² /640ac

Designer	Stormwater Management Area 'A'
Notes:	<p>ADS Stormtech SC-3500 Infiltration System</p> <p>ADS Stormtech SC-740 Isolator Row Sizing:</p> <ul style="list-style-type: none"> Two isolator rows are provided (total units = 21). Treated flow rate = 0.40 CFS / unit X 21 units = 8.40 CFS Treated flow rate > WQF (Inflow rate from 100-year storm event = 6.83 CFS) q_u obtained from exhibit 4-III for NRCS type III rainfall distribution



Exhibit 4-III Unit peak discharge (q_u) for NRCS (SCS) type III rainfall distribution



WQV & WQF CALCULATIONS - STORMWATER MANAGEMENT AREA 'B'

Project: 446 Hopmeadow Street, Simsbury	Calculated By	Date
Client: Vessel Technologies, Inc.	SMM	12/14/2022

Water Quality Volume (WQV)

0.62 ac	A = Area draining to the practice
0.32 ac	A_i = Impervious area draining to the practice
0.52 decimal	I = Percent impervious area draining to the practice, in decimal form
0.52 unitless	R_v = Runoff coefficient = $0.05 + (0.9 \times I)$
0.32 ac-in	$WQV = 1" \times R_v \times A$
1,167 cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")

Water Quality Flow (WQF)

1.00 inches	P = amount of rainfall.
0.52 inches	Q = Water Quality Depth. $Q = WQV / A$
94 unitless	CN = unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 \cdot [Q^2 + 1.25 \cdot Q \cdot P]^{0.5})$
0.6 inches	S = potential maximum retention. $S = (1000 / CN) - 10$
0.121 inches	I_a = initial abstraction. $I_a = 0.2S$
minutes	T_c = Time of Concentration
cfs/mi ² /in	qu is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
0.000 cfs	$WQF = qu \times WQV$. Conversion: to convert "cfs/mi ² /in" * ac-in" to "cfs" multiply by 1mi ² /640ac

Designer	Stormwater Management Area 'B'
Notes:	<p>Bioretention Basin</p> <p>Treated volume (volume stored prior to discharging) = 4,315 CF</p> <p>Contributing WQV = 1,157 CF</p> <p>Treated volume = 373% of Water Quality Volume</p>



WQV & WQF CALCULATIONS - STORMWATER MANAGEMENT AREA 'C'

Project: 446 Hopmeadow Street, Simsbury	Calculated By	Date
Client: Vessel Technologies, Inc.	SMM	12/14/2022

Water Quality Volume (WQV)

1.68 ac	A = Area draining to the practice
0.20 ac	A_i = Impervious area draining to the practice
0.12 decimal	I = Percent impervious area draining to the practice, in decimal form
0.16 unitless	R_v = Runoff coefficient = $0.05 + (0.9 \times I)$
0.26 ac-in	$WQV = 1" \times R_v \times A$
958 cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")

Water Quality Flow (WQF)

1.00 inches	P = amount of rainfall.
0.16 inches	Q = Water Quality Depth. $Q = WQV / A$
84 unitless	CN = unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 \cdot [Q^2 + 1.25 \cdot Q \cdot P]^{0.5})$
1.9 inches	S = potential maximum retention. $S = (1000 / CN) - 10$
0.374 inches	I_a = initial abstraction. $I_a = 0.2S$
minutes	T_c = Time of Concentration
cfs/mi ² /in	q_u is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
0.000 cfs	$WQF = q_u \times WQV$. Conversion: to convert "cfs/mi ² /in" * ac-in" to "cfs" multiply by 1mi ² /640ac

Designer	Stormwater Management Area 'C'
Notes:	<p>Drywell and Collection Basin</p> <p>Treated volume (volume stored through 100-yr event) = 1,656 CF</p> <p>Contributing WQV = 958 CF</p> <p>Treated volume = 173% of Water Quality Volume</p>



WQV & WQF CALCULATIONS - STORMWATER MANAGEMENT AREA 'D'

Project: 446 Hopmeadow Street, Simsbury	Calculated By	Date
Client: Vessel Technologies, Inc.	SMM	12/14/2022

Water Quality Volume (WQV)

0.32 ac	A = Area draining to the practice
0.03 ac	A_i = Impervious area draining to the practice
0.09 decimal	I = Percent impervious area draining to the practice, in decimal form
0.13 unitless	R_v = Runoff coefficient = $0.05 + (0.9 \times I)$
0.04 ac-in	$WQV = 1" \times R_v \times A$
156 cf	WQV conversion (ac-in x 43,560 sf/ac x 1ft/12")

Water Quality Flow (WQF)

1.00 inches	P = amount of rainfall.
0.13 inches	Q = Water Quality Depth. $Q = WQV / A$
83 unitless	CN = unit peak discharge curve number. $CN = 1000 / (10 + 5P + 10Q - 10 \cdot [Q^2 + 1.25 \cdot Q \cdot P]^{0.5})$
2.0 inches	S = potential maximum retention. $S = (1000 / CN) - 10$
0.407 inches	I_a = initial abstraction. $I_a = 0.2S$
minutes	T_c = Time of Concentration
cfs/mi ² /in	q_u is the unit peak discharge. Obtain this value from TR-55 exhibits 4-II and 4-III
0.000 cfs	$WQF = q_u \times WQV$. Conversion: to convert "cfs/mi ² /in" * ac-in" to "cfs" multiply by 1mi ² /640ac

Designer	Stormwater Management Area 'C'
Notes:	<p>Drywell and Collection Basin</p> <p>Treated volume (volume stored through 100-yr event) = 393 CF</p> <p>Contributing WQV = 156 CF</p> <p>Treated volume = 252% of Water Quality Volume</p>



Appendix B – Riprap Apron Design

Outlet Protection Design

Outlet EW-1

Reference: Connecticut Department of Transportation Drainage Manual, Dated October 2000

- A. Apron width at culvert end (W_1) = 3 Sp where Sp = outlet pipe diameter
- B. Apron length (La) = $\frac{1.8(Q-5)}{(Sp)^{3/2}} + 10$
- C. Apron width at downstream end (W) = 3Sp + 0.7La where La = apron length

Type A Riprap Apron (Tailwater Condition) : TW < 0.5 dia of outlet

Peak Q(25yr)= cfs PIPE DIA= ft

A. $W_1 = 3(Sp) =$ ft

B. $La = \frac{1.8(Q-5)}{(Sp)^{1.5}} + 10 =$ ft Use 5' min.

C. $W_2 = 3(Sp) + 0.7(La) =$ ft

Table 11.11 Allowable Outlet Velocities for Type A and B Riprap Aprons

Outlet Velocity - mps (fps)	Riprap Specification
0-2.44 (0-8)	Modified
2.44-3.05 (8-10)	Intermediate
3.05-4.27 (10-14)	Standard

V(25yr)= fps Therefore; Use Modified Riprap

Outlet Protection Design

Outlet FES-1

Reference: Connecticut Department of Transportation Drainage Manual, Dated October 2000

- A. Apron width at culvert end (W_1) = 3 Sp where Sp = outlet pipe diameter
- B. Apron length (La) = $\frac{1.8(Q-5)}{(Sp)^{3/2}} + 10$
- C. Apron width at downstream end (W) = 3Sp + 0.7La where La = apron length

Type A Riprap Apron (Tailwater Condition) : TW < 0.5 dia of outlet

Peak Q(25yr)= cfs PIPE DIA= ft

A. $W_1 = 3(Sp) =$ ft

B. La = $\frac{1.8(Q-5)}{(Sp)^{1.5}} + 10 =$ ft Use 5' min.

C. $W_2 = 3(Sp) + 0.7(La) =$ ft Use 5' min.

Table 11.11 Allowable Outlet Velocities for Type A and B Riprap Aprons

Outlet Velocity - mps (fps)	Riprap Specification
0-2.44 (0-8)	Modified
2.44-3.05 (8-10)	Intermediate
3.05-4.27 (10-14)	Standard

V(25yr)= fps Therefore; Use Modified Riprap

Outlet Protection Design

Outlet FES-2

Reference: Connecticut Department of Transportation Drainage Manual, Dated October 2000

- A. Apron width at culvert end (W_1) = 3 Sp where Sp = outlet pipe diameter
- B. Apron length (La) = $\frac{1.8(Q-5)}{(Sp)^{3/2}} + 10$
- C. Apron width at downstream end (W) = 3Sp + 0.7La where La = apron length

Type A Riprap Apron (Tailwater Condition) : TW < 0.5 dia of outlet

Peak Q(25yr)= cfs PIPE DIA= ft

A. $W_1 = 3(Sp) =$ ft

B. La = $\frac{1.8(Q-5)}{(Sp)^{1.5}} + 10 =$ ft




C. $W_2 = 3(Sp) + 0.7(La) =$ ft

Table 11.11 Allowable Outlet Velocities for Type A and B Riprap Aprons

Outlet Velocity - mps (fps)	Riprap Specification
0-2.44 (0-8)	Modified
2.44-3.05 (8-10)	Intermediate
3.05-4.27 (10-14)	Standard

V(25yr)= fps Therefore; Use Modified Riprap

**Appendix C –
Pre-Development
HydroCAD Report**



pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 2

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	WQV	Type III 24-hr		Default	24.00	1	1.00	2
2	2-Year	Type III 24-hr		Default	24.00	1	3.32	2
3	10-Year	Type III 24-hr		Default	24.00	1	5.35	2
4	25-Year	Type III 24-hr		Default	24.00	1	6.61	2
5	100-Year	Type III 24-hr		Default	24.00	1	8.56	2

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 3

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
684	76	Gravel roads, HSG A (DA1)
108,124	39	Pasture/grassland/range, Good, HSG A (DA1)
11,948	98	Paved parking, HSG A (DA1)
4,938	98	Roofs, HSG A (DA1)
77,918	30	Woods, Good, HSG A (DA1)
203,612	41	TOTAL AREA

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 4

Soil Listing (all nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
203,612	HSG A	DA1
0	HSG B	
0	HSG C	
0	HSG D	
0	Other	
203,612		TOTAL AREA

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 5

Ground Covers (all nodes)

HSG-A (sq-ft)	HSG-B (sq-ft)	HSG-C (sq-ft)	HSG-D (sq-ft)	Other (sq-ft)	Total (sq-ft)	Ground Cover
684	0	0	0	0	684	Gravel roads
108,124	0	0	0	0	108,124	Pasture/grassland/range, Good
11,948	0	0	0	0	11,948	Paved parking
4,938	0	0	0	0	4,938	Roofs
77,918	0	0	0	0	77,918	Woods, Good
203,612	0	0	0	0	203,612	TOTAL AREA

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 6

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1: DA1

Runoff Area=203,612 sf 8.29% Impervious Runoff Depth=0.00"
Flow Length=764' Tc=22.5 min CN=41 Runoff=0.00 cfs 0 cf

Link AP: Analysis Point

Inflow=0.00 cfs 0 cf
Primary=0.00 cfs 0 cf

Total Runoff Area = 203,612 sf Runoff Volume = 0 cf Average Runoff Depth = 0.00"
91.71% Pervious = 186,726 sf 8.29% Impervious = 16,886 sf

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 7

Summary for Subcatchment DA1: DA1

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr WQV Rainfall=1.00"

Area (sf)	CN	Description
108,124	39	Pasture/grassland/range, Good, HSG A
11,948	98	Paved parking, HSG A
77,918	30	Woods, Good, HSG A
4,938	98	Roofs, HSG A
684	76	Gravel roads, HSG A
203,612	41	Weighted Average
186,726		91.71% Pervious Area
16,886		8.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
2.0	127	0.0450	1.06		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
1.5	136	0.0441	1.47		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
3.4	283	0.0750	1.37		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
22.5	764	Total			

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 8

Summary for Link AP: Analysis Point

Inflow Area = 203,612 sf, 8.29% Impervious, Inflow Depth = 0.00" for WQV event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

pre development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 9

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1: DA1

Runoff Area=203,612 sf 8.29% Impervious Runoff Depth=0.01"
Flow Length=764' Tc=22.5 min CN=41 Runoff=0.01 cfs 223 cf

Link AP: Analysis Point

Inflow=0.01 cfs 223 cf
Primary=0.01 cfs 223 cf

Total Runoff Area = 203,612 sf Runoff Volume = 223 cf Average Runoff Depth = 0.01"
91.71% Pervious = 186,726 sf 8.29% Impervious = 16,886 sf

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 10

Summary for Subcatchment DA1: DA1

Runoff = 0.01 cfs @ 21.88 hrs, Volume= 223 cf, Depth= 0.01"
 Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 2-Year Rainfall=3.32"

Area (sf)	CN	Description
108,124	39	Pasture/grassland/range, Good, HSG A
11,948	98	Paved parking, HSG A
77,918	30	Woods, Good, HSG A
4,938	98	Roofs, HSG A
684	76	Gravel roads, HSG A
203,612	41	Weighted Average
186,726		91.71% Pervious Area
16,886		8.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
2.0	127	0.0450	1.06		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
1.5	136	0.0441	1.47		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
3.4	283	0.0750	1.37		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
22.5	764	Total			

pre development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 11

Summary for Link AP: Analysis Point

Inflow Area = 203,612 sf, 8.29% Impervious, Inflow Depth = 0.01" for 2-Year event
Inflow = 0.01 cfs @ 21.88 hrs, Volume= 223 cf
Primary = 0.01 cfs @ 21.88 hrs, Volume= 223 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

pre development

Type III 24-hr 10-Year Rainfall=5.35"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 12

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1: DA1

Runoff Area=203,612 sf 8.29% Impervious Runoff Depth=0.36"
Flow Length=764' Tc=22.5 min CN=41 Runoff=0.50 cfs 6,149 cf

Link AP: Analysis Point

Inflow=0.50 cfs 6,149 cf
Primary=0.50 cfs 6,149 cf

Total Runoff Area = 203,612 sf Runoff Volume = 6,149 cf Average Runoff Depth = 0.36"
91.71% Pervious = 186,726 sf 8.29% Impervious = 16,886 sf

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 13

Summary for Subcatchment DA1: DA1

Runoff = 0.50 cfs @ 12.61 hrs, Volume= 6,149 cf, Depth= 0.36"
 Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 10-Year Rainfall=5.35"

Area (sf)	CN	Description
108,124	39	Pasture/grassland/range, Good, HSG A
11,948	98	Paved parking, HSG A
77,918	30	Woods, Good, HSG A
4,938	98	Roofs, HSG A
684	76	Gravel roads, HSG A
203,612	41	Weighted Average
186,726		91.71% Pervious Area
16,886		8.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
2.0	127	0.0450	1.06		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
1.5	136	0.0441	1.47		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
3.4	283	0.0750	1.37		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
22.5	764	Total			

Summary for Link AP: Analysis Point

Inflow Area = 203,612 sf, 8.29% Impervious, Inflow Depth = 0.36" for 10-Year event
Inflow = 0.50 cfs @ 12.61 hrs, Volume= 6,149 cf
Primary = 0.50 cfs @ 12.61 hrs, Volume= 6,149 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

pre development

Type III 24-hr 25-Year Rainfall=6.61"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 15

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1: DA1

Runoff Area=203,612 sf 8.29% Impervious Runoff Depth=0.77"
Flow Length=764' Tc=22.5 min CN=41 Runoff=1.61 cfs 13,040 cf

Link AP: Analysis Point

Inflow=1.61 cfs 13,040 cf
Primary=1.61 cfs 13,040 cf

Total Runoff Area = 203,612 sf Runoff Volume = 13,040 cf Average Runoff Depth = 0.77"
91.71% Pervious = 186,726 sf 8.29% Impervious = 16,886 sf

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 16

Summary for Subcatchment DA1: DA1

Runoff = 1.61 cfs @ 12.49 hrs, Volume= 13,040 cf, Depth= 0.77"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 25-Year Rainfall=6.61"

Area (sf)	CN	Description
108,124	39	Pasture/grassland/range, Good, HSG A
11,948	98	Paved parking, HSG A
77,918	30	Woods, Good, HSG A
4,938	98	Roofs, HSG A
684	76	Gravel roads, HSG A
203,612	41	Weighted Average
186,726		91.71% Pervious Area
16,886		8.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
2.0	127	0.0450	1.06		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
1.5	136	0.0441	1.47		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
3.4	283	0.0750	1.37		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
22.5	764	Total			

pre development

Type III 24-hr 25-Year Rainfall=6.61"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 17

Summary for Link AP: Analysis Point

Inflow Area = 203,612 sf, 8.29% Impervious, Inflow Depth = 0.77" for 25-Year event
Inflow = 1.61 cfs @ 12.49 hrs, Volume= 13,040 cf
Primary = 1.61 cfs @ 12.49 hrs, Volume= 13,040 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

pre development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 18

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1: DA1

Runoff Area=203,612 sf 8.29% Impervious Runoff Depth=1.61"
Flow Length=764' Tc=22.5 min CN=41 Runoff=4.45 cfs 27,291 cf

Link AP: Analysis Point

Inflow=4.45 cfs 27,291 cf
Primary=4.45 cfs 27,291 cf

Total Runoff Area = 203,612 sf Runoff Volume = 27,291 cf Average Runoff Depth = 1.61"
91.71% Pervious = 186,726 sf 8.29% Impervious = 16,886 sf

pre development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 19

Summary for Subcatchment DA1: DA1

Runoff = 4.45 cfs @ 12.39 hrs, Volume= 27,291 cf, Depth= 1.61"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 100-Year Rainfall=8.56"

Area (sf)	CN	Description
108,124	39	Pasture/grassland/range, Good, HSG A
11,948	98	Paved parking, HSG A
77,918	30	Woods, Good, HSG A
4,938	98	Roofs, HSG A
684	76	Gravel roads, HSG A
203,612	41	Weighted Average
186,726		91.71% Pervious Area
16,886		8.29% Impervious Area




Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
2.0	127	0.0450	1.06		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
1.5	136	0.0441	1.47		Shallow Concentrated Flow, shallow Short Grass Pasture Kv= 7.0 fps
3.4	283	0.0750	1.37		Shallow Concentrated Flow, shallow Woodland Kv= 5.0 fps
22.5	764	Total			

Summary for Link AP: Analysis Point

Inflow Area = 203,612 sf, 8.29% Impervious, Inflow Depth = 1.61" for 100-Year event
Inflow = 4.45 cfs @ 12.39 hrs, Volume= 27,291 cf
Primary = 4.45 cfs @ 12.39 hrs, Volume= 27,291 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

**Appendix D –
Post-Development
HydroCAD Report**



Routing Diagram for post development
 Prepared by HH Engineering Assoc, Printed 12/14/2022
 HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 2

Rainfall Events Listing

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	WQV	Type III 24-hr		Default	24.00	1	1.00	2
2	1-Year	Type III 24-hr		Default	24.00	1	2.65	2
3	2-Year	Type III 24-hr		Default	24.00	1	3.32	2
4	5-Year	Type III 24-hr		Default	24.00	1	4.43	2
5	10-Year	Type III 24-hr		Default	24.00	1	5.35	2
6	25-Year	Type III 24-hr		Default	24.00	1	6.61	2
7	50-Year	Type III 24-hr		Default	24.00	1	7.53	2
8	100-Year	Type III 24-hr		Default	24.00	1	8.56	2

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 3

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
80,497	39	>75% Grass cover, Good, HSG A (DA1A, DA1B, DA2B, DA3, DA4, DA5)
47,330	98	Paved parking, HSG A (DA1A, DA1B, DA3, DA4, DA5)
14,063	98	Roofs, HSG A (DA2A)
61,709	30	Woods, Good, HSG A (DA1A, DA1B, DA2B, DA3, DA5)
203,599	54	TOTAL AREA

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 4

Soil Listing (all nodes)

Area (sq-ft)	Soil Group	Subcatchment Numbers
203,599	HSG A	DA1A, DA1B, DA2A, DA2B, DA3, DA4, DA5
0	HSG B	
0	HSG C	
0	HSG D	
0	Other	
203,599		TOTAL AREA

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 5

Ground Covers (all nodes)

HSG-A (sq-ft)	HSG-B (sq-ft)	HSG-C (sq-ft)	HSG-D (sq-ft)	Other (sq-ft)	Total (sq-ft)	Ground Cover
80,497	0	0	0	0	80,497	>75% Grass cover, Good
47,330	0	0	0	0	47,330	Paved parking
14,063	0	0	0	0	14,063	Roofs
61,709	0	0	0	0	61,709	Woods, Good
203,599	0	0	0	0	203,599	TOTAL AREA

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Printed 12/14/2022

Page 6

Pipe Listing (all nodes)

Line#	Node Number	In-Invert (feet)	Out-Invert (feet)	Length (feet)	Slope (ft/ft)	n	Width (inches)	Diam/Height (inches)	Inside-Fill (inches)
1	SW-A	84.70	84.10	44.0	0.0136	0.012	0.0	12.0	0.0
2	SW-B	90.00	87.00	125.0	0.0240	0.010	0.0	12.0	0.0

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 7

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1,366 ac 10.54% Impervious Runoff Depth=0.00"
Flow Length=337' Tc=17.4 min CN=42 Runoff=0.00 cfs 0 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=0.00"
Tc=10.0 min CN=47 Runoff=0.00 cfs 0 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=0.79"
Tc=5.0 min CN=98 Runoff=0.30 cfs 927 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=0.00"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.00 cfs 0 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=0.00"
Tc=10.0 min CN=41 Runoff=0.00 cfs 0 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=0.32"
Tc=10.0 min CN=90 Runoff=0.30 cfs 1,129 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=0.00"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.00 cfs 0 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.00' Max Vel=0.00 fps Inflow=0.00 cfs 0 cf
n=0.033 L=163.0' S=0.0166 '/ Capacity=45.63 cfs Outflow=0.00 cfs 0 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=84.72' Storage=14 cf Inflow=0.30 cfs 1,129 cf
Discarded=0.30 cfs 1,129 cf Primary=0.00 cfs 0 cf Outflow=0.30 cfs 1,129 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=91.24' Storage=267 cf Inflow=0.30 cfs 927 cf
Discarded=0.05 cfs 927 cf Primary=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.05 cfs 927 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=89.10' Storage=0 cf Inflow=0.00 cfs 0 cf
Discarded=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.00 cfs 0 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=91.50' Storage=0 cf Inflow=0.00 cfs 0 cf
Discarded=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.00 cfs 0 cf

Link AP: Analysis Point Inflow=0.00 cfs 0 cf
Primary=0.00 cfs 0 cf

Total Runoff Area = 203,599 sf Runoff Volume = 2,056 cf Average Runoff Depth = 0.12"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Summary for Subcatchment DA1A: DA1A

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"
 Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr WQV Rainfall=1.00"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 9

Summary for Subcatchment DA1B: DA1B

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr WQV Rainfall=1.00"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 10

Summary for Subcatchment DA2A: DA2A

Runoff = 0.30 cfs @ 12.07 hrs, Volume= 927 cf, Depth= 0.79"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr WQV Rainfall=1.00"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 11

Summary for Subcatchment DA2B: DA2B

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr WQV Rainfall=1.00"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 12

Summary for Subcatchment DA3: DA3

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr WQV Rainfall=1.00"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 13

Summary for Subcatchment DA4: DA4

Runoff = 0.30 cfs @ 12.15 hrs, Volume= 1,129 cf, Depth= 0.32"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr WQV Rainfall=1.00"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc
 HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 14

Summary for Subcatchment DA5: DA5

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"
 Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr WQV Rainfall=1.00"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 15


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 0.00" for WQV event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Outflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 0.00 fps, Min. Travel Time= 0.0 min
Avg. Velocity = 0.00 fps, Avg. Travel Time= 0.0 min

Peak Storage= 0 cf @ 0.00 hrs
Average Depth at Peak Storage= 0.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 16

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 17

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 0.32" for WQV event
 Inflow = 0.30 cfs @ 12.15 hrs, Volume= 1,129 cf
 Outflow = 0.30 cfs @ 12.16 hrs, Volume= 1,129 cf, Atten= 1%, Lag= 0.9 min
 Discarded = 0.30 cfs @ 12.16 hrs, Volume= 1,129 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 84.72' @ 12.16 hrs Surf.Area= 1,761 sf Storage= 14 cf

Plug-Flow detention time= 0.8 min calculated for 1,129 cf (100% of inflow)
 Center-of-Mass det. time= 0.8 min (867.3 - 866.5)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 12.16 hrs HW=84.72' (Free Discharge)
 ↳ **5=Exfiltration** (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=84.70' (Free Discharge)
 ↳ **1=Outlet Pipe** (Controls 0.00 cfs)
 ↳ **2=Low Flow Orifice** (Controls 0.00 cfs)
 ↳ **3=Upper Orifice** (Controls 0.00 cfs)
 ↳ **4=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 18

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af



Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 19

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Type III 24-hr WQV Rainfall=1.00"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 20

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 0.41" for WQV event
 Inflow = 0.30 cfs @ 12.07 hrs, Volume= 927 cf
 Outflow = 0.05 cfs @ 12.51 hrs, Volume= 927 cf, Atten= 82%, Lag= 26.3 min
 Discarded = 0.05 cfs @ 12.51 hrs, Volume= 927 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 91.24' @ 12.51 hrs Surf.Area= 1,180 sf Storage= 267 cf

Plug-Flow detention time= 34.6 min calculated for 927 cf (100% of inflow)
 Center-of-Mass det. time= 34.6 min (821.5 - 786.9)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.05 cfs @ 12.51 hrs HW=91.24' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.05 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.00 cfs of 2.67 cfs potential flow)
 ↑2=Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 21

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Type III 24-hr WQV Rainfall=1.00"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 22

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 0.00" for WQV event
 Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Outflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 89.10' @ 0.00 hrs Surf.Area= 31 sf Storage= 0 cf

Plug-Flow detention time= (not calculated: initial storage exceeds outflow)
 Center-of-Mass det. time= (not calculated: no inflow)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50			
Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68			
2.72 2.81 2.92 2.97 3.07 3.32			

Discarded OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑1=Exfiltration (Passes 0.00 cfs of 0.01 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 23

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Type III 24-hr WQV Rainfall=1.00"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 24

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 0.00" for WQV event
 Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Outflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 91.50' @ 0.00 hrs Surf.Area= 31 sf Storage= 0 cf

Plug-Flow detention time= (not calculated: initial storage exceeds outflow)
 Center-of-Mass det. time= (not calculated: no inflow)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑1=Exfiltration (Passes 0.00 cfs of 0.01 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 25

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr WQV Rainfall=1.00"

Printed 12/14/2022

Page 26

Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 0.00" for WQV event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 27

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1.366 ac 10.54% Impervious Runoff Depth=0.00"
Flow Length=337' Tc=17.4 min CN=42 Runoff=0.00 cfs 0 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=0.01"
Tc=10.0 min CN=47 Runoff=0.00 cfs 15 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=2.42"
Tc=5.0 min CN=98 Runoff=0.85 cfs 2,836 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=0.00"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.00 cfs 0 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=0.00"
Tc=10.0 min CN=41 Runoff=0.00 cfs 0 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=1.67"
Tc=10.0 min CN=90 Runoff=1.65 cfs 5,873 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=0.00"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.00 cfs 0 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.00' Max Vel=0.71 fps Inflow=0.00 cfs 15 cf
n=0.033 L=163.0' S=0.0166 '/' Capacity=45.63 cfs Outflow=0.00 cfs 15 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=85.49' Storage=591 cf Inflow=1.65 cfs 5,873 cf
Discarded=0.82 cfs 5,873 cf Primary=0.00 cfs 0 cf Outflow=0.82 cfs 5,873 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=91.86' Storage=1,118 cf Inflow=0.85 cfs 2,836 cf
Discarded=0.07 cfs 2,836 cf Primary=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.07 cfs 2,836 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=89.10' Storage=0 cf Inflow=0.00 cfs 15 cf
Discarded=0.00 cfs 15 cf Secondary=0.00 cfs 0 cf Outflow=0.00 cfs 15 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=91.50' Storage=0 cf Inflow=0.00 cfs 0 cf
Discarded=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.00 cfs 0 cf

Link AP: Analysis Point Inflow=0.00 cfs 0 cf
Primary=0.00 cfs 0 cf

Total Runoff Area = 203,599 sf Runoff Volume = 8,724 cf Average Runoff Depth = 0.51"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 28

Summary for Subcatchment DA1A: DA1A

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 1-Year Rainfall=2.65"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 29

Summary for Subcatchment DA1B: DA1B

Runoff = 0.00 cfs @ 21.27 hrs, Volume= 15 cf, Depth= 0.01"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 1-Year Rainfall=2.65"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 30

Summary for Subcatchment DA2A: DA2A

Runoff = 0.85 cfs @ 12.07 hrs, Volume= 2,836 cf, Depth= 2.42"
Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 1-Year Rainfall=2.65"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 31

Summary for Subcatchment DA2B: DA2B

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 1-Year Rainfall=2.65"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 32

Summary for Subcatchment DA3: DA3

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"
Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 1-Year Rainfall=2.65"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 33

Summary for Subcatchment DA4: DA4

Runoff = 1.65 cfs @ 12.14 hrs, Volume= 5,873 cf, Depth= 1.67"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 1-Year Rainfall=2.65"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 34

Summary for Subcatchment DA5: DA5

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 1-Year Rainfall=2.65"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 35


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 0.01" for 1-Year event
Inflow = 0.00 cfs @ 21.27 hrs, Volume= 15 cf
Outflow = 0.00 cfs @ 21.30 hrs, Volume= 15 cf, Atten= 0%, Lag= 1.8 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 0.71 fps, Min. Travel Time= 3.8 min
Avg. Velocity = 0.71 fps, Avg. Travel Time= 3.8 min

Peak Storage= 0 cf @ 21.30 hrs
Average Depth at Peak Storage= 0.00' , Surface Width= 2.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 36

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 37

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 1.67" for 1-Year event
 Inflow = 1.65 cfs @ 12.14 hrs, Volume= 5,873 cf
 Outflow = 0.82 cfs @ 12.02 hrs, Volume= 5,873 cf, Atten= 51%, Lag= 0.0 min
 Discarded = 0.82 cfs @ 12.02 hrs, Volume= 5,873 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 85.49' @ 12.37 hrs Surf.Area= 1,761 sf Storage= 591 cf

Plug-Flow detention time= 3.5 min calculated for 5,872 cf (100% of inflow)
 Center-of-Mass det. time= 3.5 min (821.6 - 818.1)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 12.02 hrs HW=84.76' (Free Discharge)
 ↳ **5=Exfiltration** (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=84.70' (Free Discharge)
 ↳ **1=Outlet Pipe** (Controls 0.00 cfs)
 ↳ **2=Low Flow Orifice** (Controls 0.00 cfs)
 ↳ **3=Upper Orifice** (Controls 0.00 cfs)
 ↳ **4=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 38

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af



Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 39

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 40

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 1.27" for 1-Year event
 Inflow = 0.85 cfs @ 12.07 hrs, Volume= 2,836 cf
 Outflow = 0.07 cfs @ 12.95 hrs, Volume= 2,836 cf, Atten= 92%, Lag= 52.8 min
 Discarded = 0.07 cfs @ 12.95 hrs, Volume= 2,836 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 91.86' @ 12.95 hrs Surf.Area= 1,563 sf Storage= 1,118 cf

Plug-Flow detention time= 130.4 min calculated for 2,835 cf (100% of inflow)
 Center-of-Mass det. time= 130.4 min (890.0 - 759.6)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.07 cfs @ 12.95 hrs HW=91.86' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.07 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.00 cfs of 2.67 cfs potential flow)
 ↑2=Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 41

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 42

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 0.00" for 1-Year event
 Inflow = 0.00 cfs @ 21.30 hrs, Volume= 15 cf
 Outflow = 0.00 cfs @ 21.33 hrs, Volume= 15 cf, Atten= 0%, Lag= 1.5 min
 Discarded = 0.00 cfs @ 21.33 hrs, Volume= 15 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 89.10' @ 21.33 hrs Surf.Area= 31 sf Storage= 0 cf

Plug-Flow detention time= 2.0 min calculated for 15 cf (100% of inflow)
 Center-of-Mass det. time= 2.0 min (1,205.7 - 1,203.6)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50			
Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68			
2.72 2.81 2.92 2.97 3.07 3.32			

Discarded OutFlow Max=0.01 cfs @ 21.33 hrs HW=89.10' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.01 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 43

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 44

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 0.00" for 1-Year event
 Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Outflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min
 Discarded = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 91.50' @ 0.00 hrs Surf.Area= 31 sf Storage= 0 cf

Plug-Flow detention time= (not calculated: initial storage exceeds outflow)
 Center-of-Mass det. time= (not calculated: no inflow)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑1=Exfiltration (Passes 0.00 cfs of 0.01 cfs potential flow)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 1-Year Rainfall=2.65"

Printed 12/14/2022

Page 45

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Type III 24-hr 1-Year Rainfall=2.65"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 46

Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 0.00" for 1-Year event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 47

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1.366 ac 10.54% Impervious Runoff Depth=0.02"
Flow Length=337' Tc=17.4 min CN=42 Runoff=0.00 cfs 107 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=0.09"
Tc=10.0 min CN=47 Runoff=0.00 cfs 104 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=3.09"
Tc=5.0 min CN=98 Runoff=1.08 cfs 3,618 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=0.00"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.00 cfs 0 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=0.01"
Tc=10.0 min CN=41 Runoff=0.00 cfs 15 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=2.28"
Tc=10.0 min CN=90 Runoff=2.24 cfs 8,040 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=0.00"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.00 cfs 0 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.00' Max Vel=0.71 fps Inflow=0.00 cfs 104 cf
n=0.033 L=163.0' S=0.0166 '/' Capacity=45.63 cfs Outflow=0.00 cfs 104 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=85.95' Storage=1,258 cf Inflow=2.24 cfs 8,040 cf
Discarded=0.82 cfs 8,040 cf Primary=0.00 cfs 0 cf Outflow=0.82 cfs 8,040 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=92.11' Storage=1,521 cf Inflow=1.08 cfs 3,618 cf
Discarded=0.08 cfs 3,618 cf Primary=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.08 cfs 3,618 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=89.12' Storage=1 cf Inflow=0.01 cfs 212 cf
Discarded=0.01 cfs 212 cf Secondary=0.00 cfs 0 cf Outflow=0.01 cfs 212 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=91.50' Storage=0 cf Inflow=0.00 cfs 15 cf
Discarded=0.00 cfs 15 cf Secondary=0.00 cfs 0 cf Outflow=0.00 cfs 15 cf

Link AP: Analysis Point Inflow=0.00 cfs 0 cf
Primary=0.00 cfs 0 cf

Total Runoff Area = 203,599 sf Runoff Volume = 11,885 cf Average Runoff Depth = 0.70"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 48

Summary for Subcatchment DA1A: DA1A

Runoff = 0.00 cfs @ 17.42 hrs, Volume= 107 cf, Depth= 0.02"

Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 2-Year Rainfall=3.32"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 49

Summary for Subcatchment DA1B: DA1B

Runoff = 0.00 cfs @ 14.64 hrs, Volume= 104 cf, Depth= 0.09"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 2-Year Rainfall=3.32"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 50

Summary for Subcatchment DA2A: DA2A

Runoff = 1.08 cfs @ 12.07 hrs, Volume= 3,618 cf, Depth= 3.09"
Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 2-Year Rainfall=3.32"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 51

Summary for Subcatchment DA2B: DA2B

Runoff = 0.00 cfs @ 24.03 hrs, Volume= 0 cf, Depth= 0.00"
Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 2-Year Rainfall=3.32"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 52

Summary for Subcatchment DA3: DA3

Runoff = 0.00 cfs @ 21.70 hrs, Volume= 15 cf, Depth= 0.01"
Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 2-Year Rainfall=3.32"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 53

Summary for Subcatchment DA4: DA4

Runoff = 2.24 cfs @ 12.14 hrs, Volume= 8,040 cf, Depth= 2.28"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 2-Year Rainfall=3.32"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 54

Summary for Subcatchment DA5: DA5

Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 2-Year Rainfall=3.32"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 55


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 0.09" for 2-Year event
Inflow = 0.00 cfs @ 14.64 hrs, Volume= 104 cf
Outflow = 0.00 cfs @ 14.70 hrs, Volume= 104 cf, Atten= 0%, Lag= 3.5 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 0.71 fps, Min. Travel Time= 3.8 min
Avg. Velocity = 0.71 fps, Avg. Travel Time= 3.8 min

Peak Storage= 1 cf @ 14.70 hrs
Average Depth at Peak Storage= 0.00' , Surface Width= 2.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 56

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 57

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 2.28" for 2-Year event
 Inflow = 2.24 cfs @ 12.14 hrs, Volume= 8,040 cf
 Outflow = 0.82 cfs @ 11.94 hrs, Volume= 8,040 cf, Atten= 64%, Lag= 0.0 min
 Discarded = 0.82 cfs @ 11.94 hrs, Volume= 8,040 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 85.95' @ 12.47 hrs Surf.Area= 1,761 sf Storage= 1,258 cf

Plug-Flow detention time= 7.4 min calculated for 8,038 cf (100% of inflow)
 Center-of-Mass det. time= 7.4 min (816.6 - 809.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 11.94 hrs HW=84.76' (Free Discharge)
 ↳ **5=Exfiltration** (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=84.70' (Free Discharge)
 ↳ **1=Outlet Pipe** (Controls 0.00 cfs)
 ↳ **2=Low Flow Orifice** (Controls 0.00 cfs)
 ↳ **3=Upper Orifice** (Controls 0.00 cfs)
 ↳ **4=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 58

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af



Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 59

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 60

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 1.62" for 2-Year event
 Inflow = 1.08 cfs @ 12.07 hrs, Volume= 3,618 cf
 Outflow = 0.08 cfs @ 13.07 hrs, Volume= 3,618 cf, Atten= 93%, Lag= 60.3 min
 Discarded = 0.08 cfs @ 13.07 hrs, Volume= 3,618 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 92.11' @ 13.07 hrs Surf.Area= 1,721 sf Storage= 1,521 cf

Plug-Flow detention time= 170.7 min calculated for 3,617 cf (100% of inflow)
 Center-of-Mass det. time= 170.6 min (925.4 - 754.7)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/ Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.08 cfs @ 13.07 hrs HW=92.11' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.08 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.00 cfs of 2.67 cfs potential flow)
 ↑2=Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 61

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 62

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 0.03" for 2-Year event
 Inflow = 0.01 cfs @ 16.88 hrs, Volume= 212 cf
 Outflow = 0.01 cfs @ 16.91 hrs, Volume= 212 cf, Atten= 0%, Lag= 2.1 min
 Discarded = 0.01 cfs @ 16.91 hrs, Volume= 212 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 89.12' @ 16.91 hrs Surf.Area= 31 sf Storage= 1 cf

Plug-Flow detention time= 2.0 min calculated for 212 cf (100% of inflow)
 Center-of-Mass det. time= 2.0 min (1,120.5 - 1,118.5)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50			
Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68			
2.72 2.81 2.92 2.97 3.07 3.32			

Discarded OutFlow Max=0.01 cfs @ 16.91 hrs HW=89.12' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.01 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 63

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 64

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 0.01" for 2-Year event
 Inflow = 0.00 cfs @ 21.70 hrs, Volume= 15 cf
 Outflow = 0.00 cfs @ 21.74 hrs, Volume= 15 cf, Atten= 0%, Lag= 2.3 min
 Discarded = 0.00 cfs @ 21.74 hrs, Volume= 15 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 91.50' @ 21.74 hrs Surf.Area= 31 sf Storage= 0 cf

Plug-Flow detention time= 3.0 min calculated for 15 cf (100% of inflow)
 Center-of-Mass det. time= 3.0 min (1,222.7 - 1,219.6)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.01 cfs @ 21.74 hrs HW=91.50' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.01 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 2-Year Rainfall=3.32"

Printed 12/14/2022

Page 65

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Type III 24-hr 2-Year Rainfall=3.32"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 66

Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 0.00" for 2-Year event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 67

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1.366 ac 10.54% Impervious Runoff Depth=0.18"
Flow Length=337' Tc=17.4 min CN=42 Runoff=0.04 cfs 891 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=0.35"
Tc=10.0 min CN=47 Runoff=0.04 cfs 399 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=4.19"
Tc=5.0 min CN=98 Runoff=1.44 cfs 4,915 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=0.08"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.00 cfs 83 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=0.15"
Tc=10.0 min CN=41 Runoff=0.01 cfs 177 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=3.33"
Tc=10.0 min CN=90 Runoff=3.22 cfs 11,738 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=0.03"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.00 cfs 105 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.03' Max Vel=0.71 fps Inflow=0.04 cfs 399 cf
n=0.033 L=163.0' S=0.0166 '/' Capacity=45.63 cfs Outflow=0.04 cfs 399 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=86.70' Storage=2,332 cf Inflow=3.22 cfs 11,738 cf
Discarded=0.82 cfs 11,097 cf Primary=0.31 cfs 642 cf Outflow=1.12 cfs 11,738 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=92.50' Storage=2,244 cf Inflow=1.44 cfs 4,998 cf
Discarded=0.09 cfs 4,998 cf Primary=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.09 cfs 4,998 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=93.09' Storage=158 cf Inflow=0.07 cfs 1,291 cf
Discarded=0.05 cfs 1,291 cf Secondary=0.00 cfs 0 cf Outflow=0.05 cfs 1,291 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=91.54' Storage=1 cf Inflow=0.01 cfs 177 cf
Discarded=0.01 cfs 177 cf Secondary=0.00 cfs 0 cf Outflow=0.01 cfs 177 cf

Link AP: Analysis Point Inflow=0.31 cfs 746 cf
Primary=0.31 cfs 746 cf

Total Runoff Area = 203,599 sf Runoff Volume = 18,309 cf Average Runoff Depth = 1.08"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 68

Summary for Subcatchment DA1A: DA1A

Runoff = 0.04 cfs @ 12.68 hrs, Volume= 891 cf, Depth= 0.18"

Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 5-Year Rainfall=4.43"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 69

Summary for Subcatchment DA1B: DA1B

Runoff = 0.04 cfs @ 12.39 hrs, Volume= 399 cf, Depth= 0.35"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 5-Year Rainfall=4.43"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 70

Summary for Subcatchment DA2A: DA2A

Runoff = 1.44 cfs @ 12.07 hrs, Volume= 4,915 cf, Depth= 4.19"
Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 5-Year Rainfall=4.43"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 71

Summary for Subcatchment DA2B: DA2B

Runoff = 0.00 cfs @ 15.15 hrs, Volume= 83 cf, Depth= 0.08"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 5-Year Rainfall=4.43"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 72

Summary for Subcatchment DA3: DA3

Runoff = 0.01 cfs @ 13.72 hrs, Volume= 177 cf, Depth= 0.15"
Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 5-Year Rainfall=4.43"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 73

Summary for Subcatchment DA4: DA4

Runoff = 3.22 cfs @ 12.14 hrs, Volume= 11,738 cf, Depth= 3.33"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 5-Year Rainfall=4.43"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 74

Summary for Subcatchment DA5: DA5

Runoff = 0.00 cfs @ 20.85 hrs, Volume= 105 cf, Depth= 0.03"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 5-Year Rainfall=4.43"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 75


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 0.35" for 5-Year event
Inflow = 0.04 cfs @ 12.39 hrs, Volume= 399 cf
Outflow = 0.04 cfs @ 12.46 hrs, Volume= 399 cf, Atten= 4%, Lag= 3.9 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 0.71 fps, Min. Travel Time= 3.8 min
Avg. Velocity = 0.71 fps, Avg. Travel Time= 3.8 min

Peak Storage= 10 cf @ 12.46 hrs
Average Depth at Peak Storage= 0.03' , Surface Width= 2.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.43"

Printed 12/14/2022

Page 76

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 77

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 3.33" for 5-Year event
 Inflow = 3.22 cfs @ 12.14 hrs, Volume= 11,738 cf
 Outflow = 1.12 cfs @ 12.47 hrs, Volume= 11,738 cf, Atten= 65%, Lag= 20.2 min
 Discarded = 0.82 cfs @ 11.82 hrs, Volume= 11,097 cf
 Primary = 0.31 cfs @ 12.47 hrs, Volume= 642 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 86.70' @ 12.47 hrs Surf.Area= 1,761 sf Storage= 2,332 cf

Plug-Flow detention time= 12.6 min calculated for 11,735 cf (100% of inflow)
 Center-of-Mass det. time= 12.6 min (811.2 - 798.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 11.82 hrs HW=84.76' (Free Discharge)
 ↳ **5=Exfiltration** (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=0.31 cfs @ 12.47 hrs HW=86.70' (Free Discharge)
 ↳ **1=Outlet Pipe** (Passes 0.31 cfs of 4.63 cfs potential flow)
 ↳ **2=Low Flow Orifice** (Orifice Controls 0.31 cfs @ 3.51 fps)
 ↳ **3=Upper Orifice** (Controls 0.00 cfs)
 ↳ **4=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.43"

Printed 12/14/2022

Page 78

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af



Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.43"

Printed 12/14/2022

Page 79

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 80

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 2.23" for 5-Year event
 Inflow = 1.44 cfs @ 12.07 hrs, Volume= 4,998 cf
 Outflow = 0.09 cfs @ 13.50 hrs, Volume= 4,998 cf, Atten= 94%, Lag= 86.0 min
 Discarded = 0.09 cfs @ 13.50 hrs, Volume= 4,998 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 92.50' @ 13.50 hrs Surf.Area= 1,985 sf Storage= 2,244 cf

Plug-Flow detention time= 236.0 min calculated for 4,997 cf (100% of inflow)
 Center-of-Mass det. time= 236.0 min (990.8 - 754.8)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.09 cfs @ 13.50 hrs HW=92.50' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.09 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.00 cfs of 2.67 cfs potential flow)
 ↑2=Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.43"

Printed 12/14/2022

Page 81

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 82

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 0.21" for 5-Year event
 Inflow = 0.07 cfs @ 12.58 hrs, Volume= 1,291 cf
 Outflow = 0.05 cfs @ 13.61 hrs, Volume= 1,291 cf, Atten= 29%, Lag= 61.6 min
 Discarded = 0.05 cfs @ 13.61 hrs, Volume= 1,291 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 93.09' @ 13.61 hrs Surf.Area= 111 sf Storage= 158 cf

Plug-Flow detention time= 91.1 min calculated for 1,291 cf (100% of inflow)
 Center-of-Mass det. time= 91.1 min (1,093.0 - 1,001.8)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50
			Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68
			2.72 2.81 2.92 2.97 3.07 3.32

Discarded OutFlow Max=0.05 cfs @ 13.61 hrs HW=93.09' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.05 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.43"

Printed 12/14/2022

Page 83

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 84

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 0.15" for 5-Year event
 Inflow = 0.01 cfs @ 13.72 hrs, Volume= 177 cf
 Outflow = 0.01 cfs @ 13.77 hrs, Volume= 177 cf, Atten= 0%, Lag= 3.1 min
 Discarded = 0.01 cfs @ 13.77 hrs, Volume= 177 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 91.54' @ 13.77 hrs Surf.Area= 32 sf Storage= 1 cf

Plug-Flow detention time= 3.0 min calculated for 177 cf (100% of inflow)
 Center-of-Mass det. time= 3.0 min (1,031.1 - 1,028.0)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.01 cfs @ 13.77 hrs HW=91.54' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.01 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 5-Year Rainfall=4.43"

Printed 12/14/2022

Page 85

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Type III 24-hr 5-Year Rainfall=4.43"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 86

Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 0.08" for 5-Year event
Inflow = 0.31 cfs @ 12.47 hrs, Volume= 746 cf
Primary = 0.31 cfs @ 12.47 hrs, Volume= 746 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 87

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1.366 ac 10.54% Impervious Runoff Depth=0.41"
Flow Length=337' Tc=17.4 min CN=42 Runoff=0.20 cfs 2,026 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=0.67"
Tc=10.0 min CN=47 Runoff=0.12 cfs 757 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=5.11"
Tc=5.0 min CN=98 Runoff=1.75 cfs 5,992 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=0.24"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.01 cfs 252 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=0.36"
Tc=10.0 min CN=41 Runoff=0.04 cfs 424 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=4.21"
Tc=10.0 min CN=90 Runoff=4.03 cfs 14,862 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=0.13"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.02 cfs 521 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.06' Max Vel=0.93 fps Inflow=0.12 cfs 757 cf
n=0.033 L=163.0' S=0.0166 '/' Capacity=45.63 cfs Outflow=0.12 cfs 757 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=87.41' Storage=3,298 cf Inflow=4.03 cfs 14,862 cf
Discarded=0.82 cfs 13,384 cf Primary=0.47 cfs 1,477 cf Outflow=1.28 cfs 14,862 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=92.83' Storage=2,933 cf Inflow=1.75 cfs 6,244 cf
Discarded=0.10 cfs 6,244 cf Primary=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.10 cfs 6,244 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=93.41' Storage=253 cf Inflow=0.29 cfs 2,782 cf
Discarded=0.22 cfs 2,782 cf Secondary=0.00 cfs 0 cf Outflow=0.22 cfs 2,782 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=92.40' Storage=33 cf Inflow=0.04 cfs 424 cf
Discarded=0.02 cfs 424 cf Secondary=0.00 cfs 0 cf Outflow=0.02 cfs 424 cf

Link AP: Analysis Point Inflow=0.47 cfs 1,999 cf
Primary=0.47 cfs 1,999 cf

Total Runoff Area = 203,599 sf Runoff Volume = 24,833 cf Average Runoff Depth = 1.46"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 88

Summary for Subcatchment DA1A: DA1A

Runoff = 0.20 cfs @ 12.51 hrs, Volume= 2,026 cf, Depth= 0.41"

Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 10-Year Rainfall=5.35"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 89

Summary for Subcatchment DA1B: DA1B

Runoff = 0.12 cfs @ 12.21 hrs, Volume= 757 cf, Depth= 0.67"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 10-Year Rainfall=5.35"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 90

Summary for Subcatchment DA2A: DA2A

Runoff = 1.75 cfs @ 12.07 hrs, Volume= 5,992 cf, Depth= 5.11"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 10-Year Rainfall=5.35"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 91

Summary for Subcatchment DA2B: DA2B

Runoff = 0.01 cfs @ 12.54 hrs, Volume= 252 cf, Depth= 0.24"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 10-Year Rainfall=5.35"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 92

Summary for Subcatchment DA3: DA3

Runoff = 0.04 cfs @ 12.43 hrs, Volume= 424 cf, Depth= 0.36"

Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 10-Year Rainfall=5.35"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 93

Summary for Subcatchment DA4: DA4

Runoff = 4.03 cfs @ 12.14 hrs, Volume= 14,862 cf, Depth= 4.21"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 10-Year Rainfall=5.35"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 94

Summary for Subcatchment DA5: DA5

Runoff = 0.02 cfs @ 14.78 hrs, Volume= 521 cf, Depth= 0.13"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 10-Year Rainfall=5.35"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 95


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 0.67" for 10-Year event
Inflow = 0.12 cfs @ 12.21 hrs, Volume= 757 cf
Outflow = 0.12 cfs @ 12.26 hrs, Volume= 757 cf, Atten= 3%, Lag= 3.4 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 0.93 fps, Min. Travel Time= 2.9 min
Avg. Velocity = 0.72 fps, Avg. Travel Time= 3.8 min

Peak Storage= 20 cf @ 12.26 hrs
Average Depth at Peak Storage= 0.06' , Surface Width= 2.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 96

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 97

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 4.21" for 10-Year event
 Inflow = 4.03 cfs @ 12.14 hrs, Volume= 14,862 cf
 Outflow = 1.28 cfs @ 12.50 hrs, Volume= 14,862 cf, Atten= 68%, Lag= 21.6 min
 Discarded = 0.82 cfs @ 11.76 hrs, Volume= 13,384 cf
 Primary = 0.47 cfs @ 12.50 hrs, Volume= 1,477 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 87.41' @ 12.50 hrs Surf.Area= 1,761 sf Storage= 3,298 cf

Plug-Flow detention time= 16.3 min calculated for 14,858 cf (100% of inflow)
 Center-of-Mass det. time= 16.3 min (808.5 - 792.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 11.76 hrs HW=84.76' (Free Discharge)
 ↳ **5=Exfiltration** (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=0.47 cfs @ 12.50 hrs HW=87.41' (Free Discharge)
 ↳ **1=Outlet Pipe** (Passes 0.47 cfs of 5.63 cfs potential flow)
 ↳ **2=Low Flow Orifice** (Orifice Controls 0.47 cfs @ 5.37 fps)
 ↳ **3=Upper Orifice** (Controls 0.00 cfs)
 ↳ **4=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 98

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af


Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 99

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 100

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 2.79" for 10-Year event
 Inflow = 1.75 cfs @ 12.07 hrs, Volume= 6,244 cf
 Outflow = 0.10 cfs @ 13.91 hrs, Volume= 6,244 cf, Atten= 94%, Lag= 110.1 min
 Discarded = 0.10 cfs @ 13.91 hrs, Volume= 6,244 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 92.83' @ 13.91 hrs Surf.Area= 2,207 sf Storage= 2,933 cf

Plug-Flow detention time= 289.8 min calculated for 6,242 cf (100% of inflow)
 Center-of-Mass det. time= 289.8 min (1,046.3 - 756.5)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.10 cfs @ 13.91 hrs HW=92.83' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.10 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.00 cfs of 2.67 cfs potential flow)
 ↑2=Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 101

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 102

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 0.46" for 10-Year event
 Inflow = 0.29 cfs @ 12.47 hrs, Volume= 2,782 cf
 Outflow = 0.22 cfs @ 12.68 hrs, Volume= 2,782 cf, Atten= 25%, Lag= 12.6 min
 Discarded = 0.22 cfs @ 12.68 hrs, Volume= 2,782 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 93.41' @ 12.68 hrs Surf.Area= 471 sf Storage= 253 cf

Plug-Flow detention time= 46.8 min calculated for 2,782 cf (100% of inflow)
 Center-of-Mass det. time= 46.8 min (1,004.3 - 957.5)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50
			Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68
			2.72 2.81 2.92 2.97 3.07 3.32

Discarded OutFlow Max=0.22 cfs @ 12.68 hrs HW=93.41' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.22 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 103

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 104

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 0.36" for 10-Year event
 Inflow = 0.04 cfs @ 12.43 hrs, Volume= 424 cf
 Outflow = 0.02 cfs @ 13.03 hrs, Volume= 424 cf, Atten= 52%, Lag= 36.0 min
 Discarded = 0.02 cfs @ 13.03 hrs, Volume= 424 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 92.40' @ 13.03 hrs Surf.Area= 43 sf Storage= 33 cf

Plug-Flow detention time= 12.1 min calculated for 424 cf (100% of inflow)
 Center-of-Mass det. time= 12.1 min (982.5 - 970.4)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.02 cfs @ 13.03 hrs HW=92.40' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.02 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 10-Year Rainfall=5.35"

Printed 12/14/2022

Page 105

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Type III 24-hr 10-Year Rainfall=5.35"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 106

Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 0.21" for 10-Year event
Inflow = 0.47 cfs @ 12.50 hrs, Volume= 1,999 cf
Primary = 0.47 cfs @ 12.50 hrs, Volume= 1,999 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 107

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1.366 ac 10.54% Impervious Runoff Depth=0.84"
Flow Length=337' Tc=17.4 min CN=42 Runoff=0.58 cfs 4,158 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=1.21"
Tc=10.0 min CN=47 Runoff=0.30 cfs 1,378 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=6.37"
Tc=5.0 min CN=98 Runoff=2.16 cfs 7,467 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=0.57"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.07 cfs 607 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=0.77"
Tc=10.0 min CN=41 Runoff=0.13 cfs 899 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=5.44"
Tc=10.0 min CN=90 Runoff=5.14 cfs 19,188 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=0.39"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.13 cfs 1,538 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.11' Max Vel=1.28 fps Inflow=0.30 cfs 1,378 cf
n=0.033 L=163.0' S=0.0166 '/' Capacity=45.63 cfs Outflow=0.29 cfs 1,378 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=88.23' Storage=4,298 cf Inflow=5.14 cfs 19,188 cf
Discarded=0.82 cfs 16,083 cf Primary=1.34 cfs 3,105 cf Outflow=2.15 cfs 19,188 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=93.28' Storage=4,015 cf Inflow=2.16 cfs 8,074 cf
Discarded=0.12 cfs 8,074 cf Primary=0.00 cfs 0 cf Secondary=0.00 cfs 0 cf Outflow=0.12 cfs 8,074 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=93.76' Storage=548 cf Inflow=0.80 cfs 5,536 cf
Discarded=0.63 cfs 5,536 cf Secondary=0.00 cfs 0 cf Outflow=0.63 cfs 5,536 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=97.83' Storage=251 cf Inflow=0.13 cfs 899 cf
Discarded=0.03 cfs 899 cf Secondary=0.00 cfs 0 cf Outflow=0.03 cfs 899 cf

Link AP: Analysis Point Inflow=1.46 cfs 4,644 cf
Primary=1.46 cfs 4,644 cf

Total Runoff Area = 203,599 sf Runoff Volume = 35,235 cf Average Runoff Depth = 2.08"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 108

Summary for Subcatchment DA1A: DA1A

Runoff = 0.58 cfs @ 12.37 hrs, Volume= 4,158 cf, Depth= 0.84"

Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 25-Year Rainfall=6.61"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Type III 24-hr 25-Year Rainfall=6.61"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 109

Summary for Subcatchment DA1B: DA1B

Runoff = 0.30 cfs @ 12.17 hrs, Volume= 1,378 cf, Depth= 1.21"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 25-Year Rainfall=6.61"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 25-Year Rainfall=6.61"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 110

Summary for Subcatchment DA2A: DA2A

Runoff = 2.16 cfs @ 12.07 hrs, Volume= 7,467 cf, Depth= 6.37"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 25-Year Rainfall=6.61"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Type III 24-hr 25-Year Rainfall=6.61"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 111

Summary for Subcatchment DA2B: DA2B

Runoff = 0.07 cfs @ 12.40 hrs, Volume= 607 cf, Depth= 0.57"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Type III 24-hr 25-Year Rainfall=6.61"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 112

Summary for Subcatchment DA3: DA3

Runoff = 0.13 cfs @ 12.23 hrs, Volume= 899 cf, Depth= 0.77"
Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 25-Year Rainfall=6.61"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 113

Summary for Subcatchment DA4: DA4

Runoff = 5.14 cfs @ 12.13 hrs, Volume= 19,188 cf, Depth= 5.44"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 25-Year Rainfall=6.61"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 114

Summary for Subcatchment DA5: DA5

Runoff = 0.13 cfs @ 12.48 hrs, Volume= 1,538 cf, Depth= 0.39"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 25-Year Rainfall=6.61"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 115


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 1.21" for 25-Year event
Inflow = 0.30 cfs @ 12.17 hrs, Volume= 1,378 cf
Outflow = 0.29 cfs @ 12.20 hrs, Volume= 1,378 cf, Atten= 2%, Lag= 1.6 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 1.28 fps, Min. Travel Time= 2.1 min
Avg. Velocity = 0.73 fps, Avg. Travel Time= 3.7 min

Peak Storage= 37 cf @ 12.20 hrs
Average Depth at Peak Storage= 0.11' , Surface Width= 2.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 116

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 117

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 5.44" for 25-Year event
 Inflow = 5.14 cfs @ 12.13 hrs, Volume= 19,188 cf
 Outflow = 2.15 cfs @ 12.41 hrs, Volume= 19,188 cf, Atten= 58%, Lag= 16.3 min
 Discarded = 0.82 cfs @ 11.68 hrs, Volume= 16,083 cf
 Primary = 1.34 cfs @ 12.41 hrs, Volume= 3,105 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 88.23' @ 12.41 hrs Surf.Area= 1,761 sf Storage= 4,298 cf

Plug-Flow detention time= 18.5 min calculated for 19,183 cf (100% of inflow)
 Center-of-Mass det. time= 18.5 min (803.8 - 785.4)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 11.68 hrs HW=84.76' (Free Discharge)
 ↳ **5=Exfiltration** (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=1.34 cfs @ 12.41 hrs HW=88.22' (Free Discharge)
 ↳ **1=Outlet Pipe** (Passes 1.34 cfs of 6.58 cfs potential flow)
 ↳ **2=Low Flow Orifice** (Orifice Controls 0.60 cfs @ 6.91 fps)
 ↳ **3=Upper Orifice** (Orifice Controls 0.73 cfs @ 2.40 fps)
 ↳ **4=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 118

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af



Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 119

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Type III 24-hr 25-Year Rainfall=6.61"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 120

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 3.61" for 25-Year event
 Inflow = 2.16 cfs @ 12.07 hrs, Volume= 8,074 cf
 Outflow = 0.12 cfs @ 14.41 hrs, Volume= 8,074 cf, Atten= 95%, Lag= 140.2 min
 Discarded = 0.12 cfs @ 14.41 hrs, Volume= 8,074 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 93.28' @ 14.41 hrs Surf.Area= 2,531 sf Storage= 4,015 cf

Plug-Flow detention time= 360.3 min calculated for 8,074 cf (100% of inflow)
 Center-of-Mass det. time= 360.2 min (1,118.9 - 758.7)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.12 cfs @ 14.41 hrs HW=93.28' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.00 cfs of 2.67 cfs potential flow)
 ↑2=Grate (Controls 0.00 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 121

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 122

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 0.91" for 25-Year event
 Inflow = 0.80 cfs @ 12.33 hrs, Volume= 5,536 cf
 Outflow = 0.63 cfs @ 12.56 hrs, Volume= 5,536 cf, Atten= 21%, Lag= 14.1 min
 Discarded = 0.63 cfs @ 12.56 hrs, Volume= 5,536 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 93.76' @ 12.56 hrs Surf.Area= 1,367 sf Storage= 548 cf

Plug-Flow detention time= 28.2 min calculated for 5,535 cf (100% of inflow)
 Center-of-Mass det. time= 28.3 min (952.8 - 924.5)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50
			Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68
			2.72 2.81 2.92 2.97 3.07 3.32

Discarded OutFlow Max=0.63 cfs @ 12.56 hrs HW=93.76' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.63 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 123

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 124

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 0.77" for 25-Year event
 Inflow = 0.13 cfs @ 12.23 hrs, Volume= 899 cf
 Outflow = 0.03 cfs @ 13.79 hrs, Volume= 899 cf, Atten= 75%, Lag= 94.0 min
 Discarded = 0.03 cfs @ 13.79 hrs, Volume= 899 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 97.83' @ 13.79 hrs Surf.Area= 70 sf Storage= 251 cf

Plug-Flow detention time= 216.9 min calculated for 898 cf (100% of inflow)
 Center-of-Mass det. time= 216.9 min (1,147.4 - 930.5)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.03 cfs @ 13.79 hrs HW=97.83' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.03 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 25-Year Rainfall=6.61"

Printed 12/14/2022

Page 125

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Type III 24-hr 25-Year Rainfall=6.61"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 126

Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 0.48" for 25-Year event
Inflow = 1.46 cfs @ 12.41 hrs, Volume= 4,644 cf
Primary = 1.46 cfs @ 12.41 hrs, Volume= 4,644 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 127

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1.366 ac 10.54% Impervious Runoff Depth=1.22"
Flow Length=337' Tc=17.4 min CN=42 Runoff=1.00 cfs 6,068 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=1.68"
Tc=10.0 min CN=47 Runoff=0.45 cfs 1,909 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=7.29"
Tc=5.0 min CN=98 Runoff=2.46 cfs 8,544 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=0.88"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.14 cfs 943 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=1.14"
Tc=10.0 min CN=41 Runoff=0.25 cfs 1,329 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=6.34"
Tc=10.0 min CN=90 Runoff=5.94 cfs 22,369 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=0.65"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.30 cfs 2,561 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.15' Max Vel=1.49 fps Inflow=0.45 cfs 1,909 cf
n=0.033 L=163.0' S=0.0166 '/' Capacity=45.63 cfs Outflow=0.44 cfs 1,909 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=88.71' Storage=4,810 cf Inflow=5.94 cfs 22,369 cf
Discarded=0.82 cfs 17,819 cf Primary=1.94 cfs 4,550 cf Outflow=2.75 cfs 22,369 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=93.43' Storage=4,405 cf Inflow=2.49 cfs 9,487 cf
Discarded=0.12 cfs 8,865 cf Primary=0.18 cfs 622 cf Secondary=0.00 cfs 0 cf Outflow=0.30 cfs 9,487 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=93.99' Storage=934 cf Inflow=1.35 cfs 7,977 cf
Discarded=0.95 cfs 7,977 cf Secondary=0.00 cfs 0 cf Outflow=0.95 cfs 7,977 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=98.20' Storage=298 cf Inflow=0.25 cfs 1,329 cf
Discarded=0.10 cfs 1,329 cf Secondary=0.00 cfs 0 cf Outflow=0.10 cfs 1,329 cf

Link AP: Analysis Point Inflow=2.23 cfs 7,733 cf
Primary=2.23 cfs 7,733 cf

Total Runoff Area = 203,599 sf Runoff Volume = 43,723 cf Average Runoff Depth = 2.58"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 128

Summary for Subcatchment DA1A: DA1A

Runoff = 1.00 cfs @ 12.32 hrs, Volume= 6,068 cf, Depth= 1.22"

Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 50-Year Rainfall=7.53"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Type III 24-hr 50-Year Rainfall=7.53"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 129

Summary for Subcatchment DA1B: DA1B

Runoff = 0.45 cfs @ 12.16 hrs, Volume= 1,909 cf, Depth= 1.68"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 50-Year Rainfall=7.53"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 50-Year Rainfall=7.53"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 130

Summary for Subcatchment DA2A: DA2A

Runoff = 2.46 cfs @ 12.07 hrs, Volume= 8,544 cf, Depth= 7.29"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 50-Year Rainfall=7.53"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Type III 24-hr 50-Year Rainfall=7.53"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 131

Summary for Subcatchment DA2B: DA2B

Runoff = 0.14 cfs @ 12.27 hrs, Volume= 943 cf, Depth= 0.88"
Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 50-Year Rainfall=7.53"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 132

Summary for Subcatchment DA3: DA3

Runoff = 0.25 cfs @ 12.18 hrs, Volume= 1,329 cf, Depth= 1.14"

Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 50-Year Rainfall=7.53"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 133

Summary for Subcatchment DA4: DA4

Runoff = 5.94 cfs @ 12.13 hrs, Volume= 22,369 cf, Depth= 6.34"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 50-Year Rainfall=7.53"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 134

Summary for Subcatchment DA5: DA5

Runoff = 0.30 cfs @ 12.40 hrs, Volume= 2,561 cf, Depth= 0.65"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 50-Year Rainfall=7.53"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 135


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 1.68" for 50-Year event
Inflow = 0.45 cfs @ 12.16 hrs, Volume= 1,909 cf
Outflow = 0.44 cfs @ 12.18 hrs, Volume= 1,909 cf, Atten= 2%, Lag= 1.3 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 1.49 fps, Min. Travel Time= 1.8 min
Avg. Velocity = 0.75 fps, Avg. Travel Time= 3.6 min

Peak Storage= 48 cf @ 12.18 hrs
Average Depth at Peak Storage= 0.15' , Surface Width= 2.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 136

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 137

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 6.34" for 50-Year event
 Inflow = 5.94 cfs @ 12.13 hrs, Volume= 22,369 cf
 Outflow = 2.75 cfs @ 12.37 hrs, Volume= 22,369 cf, Atten= 54%, Lag= 14.1 min
 Discarded = 0.82 cfs @ 11.64 hrs, Volume= 17,819 cf
 Primary = 1.94 cfs @ 12.37 hrs, Volume= 4,550 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 88.71' @ 12.37 hrs Surf.Area= 1,761 sf Storage= 4,810 cf

Plug-Flow detention time= 18.2 min calculated for 22,362 cf (100% of inflow)
 Center-of-Mass det. time= 18.2 min (799.6 - 781.4)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/' Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 11.64 hrs HW=84.76' (Free Discharge)
 ↳ **5=Exfiltration** (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=1.93 cfs @ 12.37 hrs HW=88.71' (Free Discharge)
 ↳ **1=Outlet Pipe** (Passes 1.93 cfs of 7.08 cfs potential flow)
 ↳ **2=Low Flow Orifice** (Orifice Controls 0.67 cfs @ 7.68 fps)
 ↳ **3=Upper Orifice** (Orifice Controls 1.26 cfs @ 4.14 fps)
 ↳ **4=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 138

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af



Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 139

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 140

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 4.24" for 50-Year event
 Inflow = 2.49 cfs @ 12.07 hrs, Volume= 9,487 cf
 Outflow = 0.30 cfs @ 12.77 hrs, Volume= 9,487 cf, Atten= 88%, Lag= 42.1 min
 Discarded = 0.12 cfs @ 12.77 hrs, Volume= 8,865 cf
 Primary = 0.18 cfs @ 12.77 hrs, Volume= 622 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 93.43' @ 12.77 hrs Surf.Area= 2,642 sf Storage= 4,405 cf

Plug-Flow detention time= 358.3 min calculated for 9,484 cf (100% of inflow)
 Center-of-Mass det. time= 358.4 min (1,118.3 - 760.0)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.12 cfs @ 12.77 hrs HW=93.43' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.17 cfs @ 12.77 hrs HW=93.43' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.17 cfs of 6.48 cfs potential flow)
 ↑2=Grate (Weir Controls 0.17 cfs @ 0.61 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 141

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 142

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 1.31" for 50-Year event
 Inflow = 1.35 cfs @ 12.29 hrs, Volume= 7,977 cf
 Outflow = 0.95 cfs @ 12.56 hrs, Volume= 7,977 cf, Atten= 29%, Lag= 16.4 min
 Discarded = 0.95 cfs @ 12.56 hrs, Volume= 7,977 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 93.99' @ 12.56 hrs Surf.Area= 2,061 sf Storage= 934 cf

Plug-Flow detention time= 23.4 min calculated for 7,975 cf (100% of inflow)
 Center-of-Mass det. time= 23.5 min (932.9 - 909.4)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50
			Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68
			2.72 2.81 2.92 2.97 3.07 3.32

Discarded OutFlow Max=0.95 cfs @ 12.56 hrs HW=93.99' (Free Discharge)
 ↑1=**Exfiltration** (Exfiltration Controls 0.95 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=**Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 143

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 144

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 1.14" for 50-Year event
 Inflow = 0.25 cfs @ 12.18 hrs, Volume= 1,329 cf
 Outflow = 0.10 cfs @ 12.61 hrs, Volume= 1,329 cf, Atten= 59%, Lag= 25.9 min
 Discarded = 0.10 cfs @ 12.61 hrs, Volume= 1,329 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 98.20' @ 12.61 hrs Surf.Area= 221 sf Storage= 298 cf

Plug-Flow detention time= 153.6 min calculated for 1,329 cf (100% of inflow)
 Center-of-Mass det. time= 153.6 min (1,066.5 - 912.9)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.10 cfs @ 12.61 hrs HW=98.20' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.10 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 50-Year Rainfall=7.53"

Printed 12/14/2022

Page 145

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Type III 24-hr 50-Year Rainfall=7.53"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 146

Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 0.80" for 50-Year event
Inflow = 2.23 cfs @ 12.37 hrs, Volume= 7,733 cf
Primary = 2.23 cfs @ 12.37 hrs, Volume= 7,733 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 147

Time span=0.00-72.00 hrs, dt=0.02 hrs, 3601 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind method - Pond routing by Stor-Ind method

Subcatchment DA1A: DA1A Runoff Area=1.366 ac 10.54% Impervious Runoff Depth=1.71"
Flow Length=337' Tc=17.4 min CN=42 Runoff=1.57 cfs 8,502 cf

Subcatchment DA1B: DA1B Runoff Area=13,628 sf 16.84% Impervious Runoff Depth=2.26"
Tc=10.0 min CN=47 Runoff=0.65 cfs 2,568 cf

Subcatchment DA2A: DA2A Runoff Area=14,063 sf 100.00% Impervious Runoff Depth=8.32"
Tc=5.0 min CN=98 Runoff=2.80 cfs 9,750 cf

Subcatchment DA2B: DA2B Runoff Area=12,794 sf 0.00% Impervious Runoff Depth=1.30"
Flow Length=189' Tc=11.5 min CN=38 Runoff=0.25 cfs 1,384 cf

Subcatchment DA3: DA3 Runoff Area=14,032 sf 9.11% Impervious Runoff Depth=1.61"
Tc=10.0 min CN=41 Runoff=0.41 cfs 1,881 cf

Subcatchment DA4: DA4 Runoff Area=42,316 sf 86.93% Impervious Runoff Depth=7.36"
Tc=10.0 min CN=90 Runoff=6.83 cfs 25,944 cf

Subcatchment DA5: DA5 Runoff Area=1.085 ac 1.47% Impervious Runoff Depth=1.00"
Flow Length=332' Tc=11.4 min CN=35 Runoff=0.56 cfs 3,949 cf

Reach CD1: CURTAIN DRAIN Avg. Flow Depth=0.19' Max Vel=1.70 fps Inflow=0.65 cfs 2,568 cf
n=0.033 L=163.0' S=0.0166 '/' Capacity=45.63 cfs Outflow=0.64 cfs 2,568 cf

Pond SW-A: Stormtech MC-3500 (SWM-A) Peak Elev=89.19' Storage=5,196 cf Inflow=6.83 cfs 25,944 cf
Discarded=0.82 cfs 19,698 cf Primary=3.44 cfs 6,247 cf Outflow=4.26 cfs 25,944 cf

Pond SW-B: Bioretention Basin (SWM-B) Peak Elev=93.50' Storage=4,576 cf Inflow=2.90 cfs 11,134 cf
Discarded=0.12 cfs 9,318 cf Primary=0.82 cfs 1,817 cf Secondary=0.00 cfs 0 cf Outflow=0.94 cfs 11,134 cf

Pond SW-C: Drywell & Basin (SWM-C) Peak Elev=94.29' Storage=1,656 cf Inflow=2.08 cfs 11,069 cf
Discarded=1.21 cfs 11,069 cf Secondary=0.00 cfs 0 cf Outflow=1.21 cfs 11,069 cf

Pond SW-D: Drywell & Basin (SWM-D) Peak Elev=98.51' Storage=393 cf Inflow=0.41 cfs 1,881 cf
Discarded=0.19 cfs 1,881 cf Secondary=0.00 cfs 0 cf Outflow=0.19 cfs 1,881 cf

Link AP: Analysis Point Inflow=4.22 cfs 12,013 cf
Primary=4.22 cfs 12,013 cf

Total Runoff Area = 203,599 sf Runoff Volume = 53,978 cf Average Runoff Depth = 3.18"
69.85% Pervious = 142,206 sf 30.15% Impervious = 61,393 sf

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 148

Summary for Subcatchment DA1A: DA1A

Runoff = 1.57 cfs @ 12.29 hrs, Volume= 8,502 cf, Depth= 1.71"

Routed to Pond SW-C : Drywell & Basin (SWM-C)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 100-Year Rainfall=8.56"

Area (ac)	CN	Description
0.673	39	>75% Grass cover, Good, HSG A
0.549	30	Woods, Good, HSG A
0.144	98	Paved parking, HSG A
1.366	42	Weighted Average
1.222		89.46% Pervious Area
0.144		10.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.7	24	0.0824	0.23		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
11.7	76	0.0485	0.11		Sheet Flow, Sheetflow Woods: Light underbrush n= 0.400 P2= 3.43"
0.6	35	0.0368	0.96		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	22	0.0345	3.77		Shallow Concentrated Flow, Shallow Paved Kv= 20.3 fps
1.5	61	0.0100	0.70		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
1.7	99	0.0394	0.99		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.1	20	0.3400	4.08		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
17.4	337	Total			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 149

Summary for Subcatchment DA1B: DA1B

Runoff = 0.65 cfs @ 12.16 hrs, Volume= 2,568 cf, Depth= 2.26"

Routed to Reach CD1 : CURTAIN DRAIN

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 100-Year Rainfall=8.56"

Area (sf)	CN	Description
8,726	39	>75% Grass cover, Good, HSG A
2,607	30	Woods, Good, HSG A
2,295	98	Paved parking, HSG A
13,628	47	Weighted Average
11,333		83.16% Pervious Area
2,295		16.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 150

Summary for Subcatchment DA2A: DA2A

Runoff = 2.80 cfs @ 12.07 hrs, Volume= 9,750 cf, Depth= 8.32"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 100-Year Rainfall=8.56"

Area (sf)	CN	Description
14,063	98	Roofs, HSG A
14,063		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Direct Entry

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 151

Summary for Subcatchment DA2B: DA2B

Runoff = 0.25 cfs @ 12.21 hrs, Volume= 1,384 cf, Depth= 1.30"

Routed to Pond SW-B : Bioretention Basin (SWM-B)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 100-Year Rainfall=8.56"

Area (sf)	CN	Description
11,225	39	>75% Grass cover, Good, HSG A
1,569	30	Woods, Good, HSG A
12,794	38	Weighted Average
12,794		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.6	100	0.0150	0.16		Sheet Flow, Sheetflow
					Grass: Short n= 0.150 P2= 3.43"
0.9	89	0.0550	1.64		Shallow Concentrated Flow, Shallow
					Short Grass Pasture Kv= 7.0 fps
11.5	189	Total			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 152

Summary for Subcatchment DA3: DA3

Runoff = 0.41 cfs @ 12.17 hrs, Volume= 1,881 cf, Depth= 1.61"
Routed to Pond SW-D : Drywell & Basin (SWM-D)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 100-Year Rainfall=8.56"

Area (sf)	CN	Description
7,100	39	>75% Grass cover, Good, HSG A
5,653	30	Woods, Good, HSG A
1,279	98	Paved parking, HSG A
14,032	41	Weighted Average
12,753		90.89% Pervious Area
1,279		9.11% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 153

Summary for Subcatchment DA4: DA4

Runoff = 6.83 cfs @ 12.13 hrs, Volume= 25,944 cf, Depth= 7.36"

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs

Type III 24-hr 100-Year Rainfall=8.56"

Area (sf)	CN	Description
5,530	39	>75% Grass cover, Good, HSG A
36,786	98	Paved parking, HSG A
42,316	90	Weighted Average
5,530		13.07% Pervious Area
36,786		86.93% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.0					Direct Entry, Direct Entry

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 154

Summary for Subcatchment DA5: DA5

Runoff = 0.56 cfs @ 12.27 hrs, Volume= 3,949 cf, Depth= 1.00"

Routed to Link AP : Analysis Point

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Type III 24-hr 100-Year Rainfall=8.56"

Area (ac)	CN	Description
0.427	39	>75% Grass cover, Good, HSG A
0.642	30	Woods, Good, HSG A
0.016	98	Paved parking, HSG A
1.085	35	Weighted Average
1.069		98.53% Pervious Area
0.016		1.47% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	18	0.1330	0.27		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
7.5	82	0.0240	0.18		Sheet Flow, Sheetflow Grass: Short n= 0.150 P2= 3.43"
1.9	118	0.0220	1.04		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.2	14	0.0500	1.12		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
0.2	32	0.1400	2.62		Shallow Concentrated Flow, Shallow Short Grass Pasture Kv= 7.0 fps
0.5	68	0.2350	2.42		Shallow Concentrated Flow, Shallow Woodland Kv= 5.0 fps
11.4	332	Total			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 155


Summary for Reach CD1: CURTAIN DRAIN

Inflow Area = 13,628 sf, 16.84% Impervious, Inflow Depth = 2.26" for 100-Year event
Inflow = 0.65 cfs @ 12.16 hrs, Volume= 2,568 cf
Outflow = 0.64 cfs @ 12.17 hrs, Volume= 2,568 cf, Atten= 1%, Lag= 1.1 min
Routed to Pond SW-C : Drywell & Basin (SWM-C)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
Max. Velocity= 1.70 fps, Min. Travel Time= 1.6 min
Avg. Velocity = 0.76 fps, Avg. Travel Time= 3.6 min

Peak Storage= 61 cf @ 12.17 hrs
Average Depth at Peak Storage= 0.19' , Surface Width= 2.00'
Bank-Full Depth= 4.50' Flow Area= 9.0 sf, Capacity= 45.63 cfs

2.00' x 4.50' deep channel, n= 0.033 Riprap, 1-inch
Length= 163.0' Slope= 0.0166 '/'
Inlet Invert= 96.00', Outlet Invert= 93.30'



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 156

Stage-Area-Storage for Reach CD1: CURTAIN DRAIN

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
96.00	0.0	0	98.60	5.2	848
96.05	0.1	16	98.65	5.3	864
96.10	0.2	33	98.70	5.4	880
96.15	0.3	49	98.75	5.5	897
96.20	0.4	65	98.80	5.6	913
96.25	0.5	82	98.85	5.7	929
96.30	0.6	98	98.90	5.8	945
96.35	0.7	114	98.95	5.9	962
96.40	0.8	130	99.00	6.0	978
96.45	0.9	147	99.05	6.1	994
96.50	1.0	163	99.10	6.2	1,011
96.55	1.1	179	99.15	6.3	1,027
96.60	1.2	196	99.20	6.4	1,043
96.65	1.3	212	99.25	6.5	1,060
96.70	1.4	228	99.30	6.6	1,076
96.75	1.5	245	99.35	6.7	1,092
96.80	1.6	261	99.40	6.8	1,108
96.85	1.7	277	99.45	6.9	1,125
96.90	1.8	293	99.50	7.0	1,141
96.95	1.9	310	99.55	7.1	1,157
97.00	2.0	326	99.60	7.2	1,174
97.05	2.1	342	99.65	7.3	1,190
97.10	2.2	359	99.70	7.4	1,206
97.15	2.3	375	99.75	7.5	1,223
97.20	2.4	391	99.80	7.6	1,239
97.25	2.5	408	99.85	7.7	1,255
97.30	2.6	424	99.90	7.8	1,271
97.35	2.7	440	99.95	7.9	1,288
97.40	2.8	456	100.00	8.0	1,304
97.45	2.9	473	100.05	8.1	1,320
97.50	3.0	489	100.10	8.2	1,337
97.55	3.1	505	100.15	8.3	1,353
97.60	3.2	522	100.20	8.4	1,369
97.65	3.3	538	100.25	8.5	1,386
97.70	3.4	554	100.30	8.6	1,402
97.75	3.5	571	100.35	8.7	1,418
97.80	3.6	587	100.40	8.8	1,434
97.85	3.7	603	100.45	8.9	1,451
97.90	3.8	619	100.50	9.0	1,467
97.95	3.9	636			
98.00	4.0	652			
98.05	4.1	668			
98.10	4.2	685			
98.15	4.3	701			
98.20	4.4	717			
98.25	4.5	734			
98.30	4.6	750			
98.35	4.7	766			
98.40	4.8	782			
98.45	4.9	799			
98.50	5.0	815			
98.55	5.1	831			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 157

Summary for Pond SW-A: Stormtech MC-3500 (SWM-A)

Inflow Area = 42,316 sf, 86.93% Impervious, Inflow Depth = 7.36" for 100-Year event
 Inflow = 6.83 cfs @ 12.13 hrs, Volume= 25,944 cf
 Outflow = 4.26 cfs @ 12.28 hrs, Volume= 25,944 cf, Atten= 38%, Lag= 8.7 min
 Discarded = 0.82 cfs @ 11.56 hrs, Volume= 19,698 cf
 Primary = 3.44 cfs @ 12.28 hrs, Volume= 6,247 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 89.19' @ 12.28 hrs Surf.Area= 1,761 sf Storage= 5,196 cf

Plug-Flow detention time= 17.8 min calculated for 25,937 cf (100% of inflow)
 Center-of-Mass det. time= 17.8 min (795.4 - 777.7)

Volume	Invert	Avail.Storage	Storage Description
#1A	84.70'	2,519 cf	22.75'W x 77.40'L x 5.50'H Field A 9,685 cf Overall - 3,388 cf Embedded = 6,297 cf x 40.0% Voids
#2A	85.45'	3,388 cf	ADS_StormTech MC-3500 d +Cap x 30 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 30 Chambers in 3 Rows Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf
		5,907 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	84.70'	12.0" Round Outlet Pipe L= 44.0' CPP, end-section conforming to fill, Ke= 0.500 Inlet / Outlet Invert= 84.70' / 84.10' S= 0.0136 '/ Cc= 0.900 n= 0.012 Corrugated PP, smooth interior, Flow Area= 0.79 sf
#2	Device 1	86.00'	4.0" Vert. Low Flow Orifice C= 0.600 Limited to weir flow at low heads
#3	Device 1	87.80'	11.0" W x 4.0" H Vert. Upper Orifice C= 0.600 Limited to weir flow at low heads
#4	Device 1	89.00'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#5	Discarded	84.70'	20.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.82 cfs @ 11.56 hrs HW=84.76' (Free Discharge)
 ↳5=Exfiltration (Exfiltration Controls 0.82 cfs)

Primary OutFlow Max=3.44 cfs @ 12.28 hrs HW=89.19' (Free Discharge)
 ↳1=Outlet Pipe (Passes 3.44 cfs of 7.55 cfs potential flow)
 ↳2=Low Flow Orifice (Orifice Controls 0.73 cfs @ 8.37 fps)
 ↳3=Upper Orifice (Orifice Controls 1.63 cfs @ 5.32 fps)
 ↳4=Sharp-Crested Rectangular Weir (Weir Controls 1.08 cfs @ 1.43 fps)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 158

Pond SW-A: Stormtech MC-3500 (SWM-A) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 3 rows = 89.4 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

10 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 75.40' Row Length +12.0" End Stone x 2 = 77.40' Base Length

3 Rows x 77.0" Wide + 9.0" Spacing x 2 + 12.0" Side Stone x 2 = 22.75' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

30 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 3 Rows = 3,388.0 cf Chamber Storage

9,684.7 cf Field - 3,388.0 cf Chambers = 6,296.7 cf Stone x 40.0% Voids = 2,518.7 cf Stone Storage

Chamber Storage + Stone Storage = 5,906.6 cf = 0.136 af



Overall Storage Efficiency = 61.0%

Overall System Size = 77.40' x 22.75' x 5.50'

30 Chambers

358.7 cy Field

233.2 cy Stone



post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 159

Stage-Area-Storage for Pond SW-A: Stormtech MC-3500 (SWM-A)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
84.70	1,761	0	89.90	1,761	5,695
84.80	1,761	70	90.00	1,761	5,766
84.90	1,761	141	90.10	1,761	5,836
85.00	1,761	211	90.20	1,761	5,907
85.10	1,761	282			
85.20	1,761	352			
85.30	1,761	423			
85.40	1,761	493			
85.50	1,761	602			
85.60	1,761	750			
85.70	1,761	897			
85.80	1,761	1,044			
85.90	1,761	1,190			
86.00	1,761	1,335			
86.10	1,761	1,480			
86.20	1,761	1,624			
86.30	1,761	1,768			
86.40	1,761	1,910			
86.50	1,761	2,052			
86.60	1,761	2,193			
86.70	1,761	2,333			
86.80	1,761	2,472			
86.90	1,761	2,610			
87.00	1,761	2,747			
87.10	1,761	2,882			
87.20	1,761	3,017			
87.30	1,761	3,150			
87.40	1,761	3,281			
87.50	1,761	3,411			
87.60	1,761	3,540			
87.70	1,761	3,667			
87.80	1,761	3,791			
87.90	1,761	3,914			
88.00	1,761	4,035			
88.10	1,761	4,153			
88.20	1,761	4,269			
88.30	1,761	4,382			
88.40	1,761	4,492			
88.50	1,761	4,599			
88.60	1,761	4,702			
88.70	1,761	4,800			
88.80	1,761	4,892			
88.90	1,761	4,976			
89.00	1,761	5,055			
89.10	1,761	5,130			
89.20	1,761	5,202			
89.30	1,761	5,273			
89.40	1,761	5,343			
89.50	1,761	5,414			
89.60	1,761	5,484			
89.70	1,761	5,554			
89.80	1,761	5,625			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 160

Summary for Pond SW-B: Bioretention Basin (SWM-B)

Inflow Area = 26,857 sf, 52.36% Impervious, Inflow Depth = 4.97" for 100-Year event
 Inflow = 2.90 cfs @ 12.07 hrs, Volume= 11,134 cf
 Outflow = 0.94 cfs @ 12.41 hrs, Volume= 11,134 cf, Atten= 67%, Lag= 20.2 min
 Discarded = 0.12 cfs @ 12.41 hrs, Volume= 9,318 cf
 Primary = 0.82 cfs @ 12.41 hrs, Volume= 1,817 cf
 Routed to Link AP : Analysis Point
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 93.50' @ 12.41 hrs Surf.Area= 2,689 sf Storage= 4,576 cf

Plug-Flow detention time= 326.5 min calculated for 11,131 cf (100% of inflow)
 Center-of-Mass det. time= 326.6 min (1,087.8 - 761.2)

Volume	Invert	Avail.Storage	Storage Description
#1	91.00'	6,325 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.00	1,031	0	0
92.00	1,649	1,340	1,340
93.00	2,324	1,987	3,327
94.00	3,055	2,690	6,016
94.10	3,132	309	6,325

Device	Routing	Invert	Outlet Devices
#1	Primary	90.00'	12.0" Round Outlet Pipe L= 125.0' CMP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 90.00' / 87.00' S= 0.0240 '/' Cc= 0.900 n= 0.010 PVC, smooth interior, Flow Area= 0.79 sf
#2	Device 1	93.40'	24.0" x 24.0" Horiz. Grate C= 0.600 Limited to weir flow at low heads
#3	Secondary	93.60'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 3.50 4.00 4.50 Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68 2.72 2.81 2.92 2.97 3.07 3.32
#4	Discarded	91.00'	2.000 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.12 cfs @ 12.41 hrs HW=93.50' (Free Discharge)
 ↑4=Exfiltration (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.81 cfs @ 12.41 hrs HW=93.50' (Free Discharge)
 ↑1=Outlet Pipe (Passes 0.81 cfs of 6.55 cfs potential flow)
 ↑2=Grate (Weir Controls 0.81 cfs @ 1.03 fps)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.00' (Free Discharge)
 ↑3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 161

Stage-Area-Storage for Pond SW-B: Bioretention Basin (SWM-B)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.00	1,031	0	93.60	2,763	4,852
91.05	1,062	52	93.65	2,799	4,992
91.10	1,093	106	93.70	2,836	5,132
91.15	1,124	162	93.75	2,872	5,275
91.20	1,155	219	93.80	2,909	5,420
91.25	1,186	277	93.85	2,945	5,566
91.30	1,216	337	93.90	2,982	5,714
91.35	1,247	399	93.95	3,018	5,864
91.40	1,278	462	94.00	3,055	6,016
91.45	1,309	527	94.05	3,093	6,170
91.50	1,340	593	94.10	3,132	6,325
91.55	1,371	661			
91.60	1,402	730			
91.65	1,433	801			
91.70	1,464	873			
91.75	1,495	947			
91.80	1,525	1,023			
91.85	1,556	1,100			
91.90	1,587	1,178			
91.95	1,618	1,258			
92.00	1,649	1,340			
92.05	1,683	1,423			
92.10	1,716	1,508			
92.15	1,750	1,595			
92.20	1,784	1,683			
92.25	1,818	1,773			
92.30	1,851	1,865			
92.35	1,885	1,958			
92.40	1,919	2,054			
92.45	1,953	2,150			
92.50	1,987	2,249			
92.55	2,020	2,349			
92.60	2,054	2,451			
92.65	2,088	2,554			
92.70	2,122	2,660			
92.75	2,155	2,767			
92.80	2,189	2,875			
92.85	2,223	2,985			
92.90	2,257	3,097			
92.95	2,290	3,211			
93.00	2,324	3,327			
93.05	2,361	3,444			
93.10	2,397	3,563			
93.15	2,434	3,683			
93.20	2,470	3,806			
93.25	2,507	3,930			
93.30	2,543	4,057			
93.35	2,580	4,185			
93.40	2,616	4,315			
93.45	2,653	4,446			
93.50	2,690	4,580			
93.55	2,726	4,715			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 162

Summary for Pond SW-C: Drywell & Basin (SWM-C)

Inflow Area = 73,131 sf, 11.72% Impervious, Inflow Depth = 1.82" for 100-Year event
 Inflow = 2.08 cfs @ 12.26 hrs, Volume= 11,069 cf
 Outflow = 1.21 cfs @ 12.60 hrs, Volume= 11,069 cf, Atten= 42%, Lag= 20.2 min
 Discarded = 1.21 cfs @ 12.60 hrs, Volume= 11,069 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routed to Pond SW-A : Stormtech MC-3500 (SWM-A)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 94.29' @ 12.60 hrs Surf.Area= 2,611 sf Storage= 1,656 cf

Plug-Flow detention time= 22.0 min calculated for 11,066 cf (100% of inflow)
 Center-of-Mass det. time= 22.0 min (919.1 - 897.1)

Volume	Invert	Avail.Storage	Storage Description
#1	89.10'	3,214 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
89.10	31	0	0
90.10	44	38	38
91.10	44	44	82
92.10	44	44	126
93.00	15	27	152
93.50	564	145	297
94.00	2,107	668	965
94.30	2,623	709	1,674
94.80	3,537	1,540	3,214

Device	Routing	Invert	Outlet Devices
#1	Discarded	89.10'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	94.30'	10.0' long x 3.0' breadth Broad-Crested Rectangular Weir
			Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00
			2.50 3.00 3.50 4.00 4.50
			Coef. (English) 2.44 2.58 2.68 2.67 2.65 2.64 2.64 2.68 2.68
			2.72 2.81 2.92 2.97 3.07 3.32

Discarded OutFlow Max=1.21 cfs @ 12.60 hrs HW=94.29' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 1.21 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=89.10' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 163

Stage-Area-Storage for Pond SW-C: Drywell & Basin (SWM-C)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
89.10	31	0	94.30	2,623	1,674
89.20	32	3	94.40	2,806	1,945
89.30	34	6	94.50	2,989	2,235
89.40	35	10	94.60	3,171	2,543
89.50	36	13	94.70	3,354	2,869
89.60	38	17	94.80	3,537	3,214
89.70	39	21			
89.80	40	25			
89.90	41	29			
90.00	43	33			
90.10	44	38			
90.20	44	42			
90.30	44	46			
90.40	44	51			
90.50	44	55			
90.60	44	60			
90.70	44	64			
90.80	44	68			
90.90	44	73			
91.00	44	77			
91.10	44	82			
91.20	44	86			
91.30	44	90			
91.40	44	95			
91.50	44	99			
91.60	44	104			
91.70	44	108			
91.80	44	112			
91.90	44	117			
92.00	44	121			
92.10	44	126			
92.20	41	130			
92.30	38	134			
92.40	34	137			
92.50	31	141			
92.60	28	143			
92.70	25	146			
92.80	21	148			
92.90	18	150			
93.00	15	152			
93.10	125	159			
93.20	235	177			
93.30	344	206			
93.40	454	246			
93.50	564	297			
93.60	873	369			
93.70	1,181	471			
93.80	1,490	605			
93.90	1,798	769			
94.00	2,107	965			
94.10	2,279	1,184			
94.20	2,451	1,420			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 164

Summary for Pond SW-D: Drywell & Basin (SWM-D)

Inflow Area = 14,032 sf, 9.11% Impervious, Inflow Depth = 1.61" for 100-Year event
 Inflow = 0.41 cfs @ 12.17 hrs, Volume= 1,881 cf
 Outflow = 0.19 cfs @ 12.54 hrs, Volume= 1,881 cf, Atten= 54%, Lag= 22.3 min
 Discarded = 0.19 cfs @ 12.54 hrs, Volume= 1,881 cf
 Secondary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link AP : Analysis Point

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs
 Peak Elev= 98.51' @ 12.54 hrs Surf.Area= 407 sf Storage= 393 cf

Plug-Flow detention time= 113.1 min calculated for 1,880 cf (100% of inflow)
 Center-of-Mass det. time= 113.1 min (1,012.1 - 899.0)

Volume	Invert	Avail.Storage	Storage Description
#1	91.50'	2,064 cf	Drywell & Basin (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
91.50	31	0	0
92.50	44	38	38
93.50	44	44	82
94.50	44	44	126
95.50	44	44	170
96.50	44	44	214
97.40	4	22	235
98.00	97	30	265
99.00	709	403	668
99.06	1,117	55	723
100.00	1,424	1,194	1,917
100.10	1,505	146	2,064

Device	Routing	Invert	Outlet Devices
#1	Discarded	91.50'	20.000 in/hr Exfiltration over Surface area
#2	Secondary	99.60'	10.0' long x 5.0' breadth Broad-Crested Rectangular Weir
Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00			
2.50 3.00 3.50 4.00 4.50 5.00 5.50			
Coef. (English) 2.34 2.50 2.70 2.68 2.68 2.66 2.65 2.65 2.65			
2.65 2.67 2.66 2.68 2.70 2.74 2.79 2.88			

Discarded OutFlow Max=0.19 cfs @ 12.54 hrs HW=98.51' (Free Discharge)
 ↑1=Exfiltration (Exfiltration Controls 0.19 cfs)

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=91.50' (Free Discharge)
 ↑2=Broad-Crested Rectangular Weir (Controls 0.00 cfs)

post development

Prepared by HH Engineering Assoc

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Type III 24-hr 100-Year Rainfall=8.56"

Printed 12/14/2022

Page 165

Stage-Area-Storage for Pond SW-D: Drywell & Basin (SWM-D)

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
91.50	31	0	96.70	35	221
91.60	32	3	96.80	31	225
91.70	34	6	96.90	26	228
91.80	35	10	97.00	22	230
91.90	36	13	97.10	17	232
92.00	38	17	97.20	13	233
92.10	39	21	97.30	8	234
92.20	40	25	97.40	4	235
92.30	41	29	97.50	19	236
92.40	43	33	97.60	35	239
92.50	44	38	97.70	51	243
92.60	44	42	97.80	66	249
92.70	44	46	97.90	82	256
92.80	44	51	98.00	97	265
92.90	44	55	98.10	158	278
93.00	44	60	98.20	219	297
93.10	44	64	98.30	281	322
93.20	44	68	98.40	342	353
93.30	44	73	98.50	403	390
93.40	44	77	98.60	464	434
93.50	44	82	98.70	525	483
93.60	44	86	98.80	587	539
93.70	44	90	98.90	648	601
93.80	44	95	99.00	709	668
93.90	44	99	99.10	1,130	768
94.00	44	104	99.20	1,163	883
94.10	44	108	99.30	1,195	1,001
94.20	44	112	99.40	1,228	1,122
94.30	44	117	99.50	1,261	1,246
94.40	44	121	99.60	1,293	1,374
94.50	44	126	99.70	1,326	1,505
94.60	44	130	99.80	1,359	1,639
94.70	44	134	99.90	1,391	1,777
94.80	44	139	100.00	1,424	1,917
94.90	44	143	100.10	1,505	2,064
95.00	44	148			
95.10	44	152			
95.20	44	156			
95.30	44	161			
95.40	44	165			
95.50	44	170			
95.60	44	174			
95.70	44	178			
95.80	44	183			
95.90	44	187			
96.00	44	192			
96.10	44	196			
96.20	44	200			
96.30	44	205			
96.40	44	209			
96.50	44	214			
96.60	40	218			

post development

Type III 24-hr 100-Year Rainfall=8.56"

Prepared by HH Engineering Assoc

Printed 12/14/2022

HydroCAD® 10.20-2g s/n 12772 © 2022 HydroCAD Software Solutions LLC

Page 166


Summary for Link AP: Analysis Point

Inflow Area = 116,436 sf, 44.27% Impervious, Inflow Depth = 1.24" for 100-Year event
Inflow = 4.22 cfs @ 12.30 hrs, Volume= 12,013 cf
Primary = 4.22 cfs @ 12.30 hrs, Volume= 12,013 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.02 hrs


REV.	DESCRIPTION OF REVISION	DATE	APPR.

POST-DEVELOPMENT DRAINAGE AREA MAP
VESSEL MULTI-FAMILY HOUSING
 PROPERTY ADDRESS
 446 HOPMEADOW STREET, SIMSBURY, CT 06089
 PREPARED FOR
VESSEL TECHNOLOGIES, INC.
 46 WEST 55TH STREET, NEW YORK, NY 10019



PROJECT NO. 2022-0013	SCALE 1" = 30'
DRAWN BY: SMM	DATE 12/16/2022
CHECKED BY: SMM	DATE 12/16/2022

DRAWING
FIGURE 4
SHEET NUMBER: 1 OF 1



PROPOSED DRAINAGE AREA 'DA4'
AREA=42,316 SQ. FT.
(IMPERVIOUS=36,786 SQ. FT.)
(GRASS=5,530 SQ. FT.)

PROPOSED DRAINAGE AREA 'DA5'
AREA=47,290 SQ. FT.
(IMPERVIOUS=691 SQ. FT.)
(GRASS=18,616 SQ. FT.)
(WOODS=27,983 SQ. FT.)

PROPOSED DRAINAGE AREA 'DA3'
AREA=14,032 SQ. FT.
(IMPERVIOUS=1,279 SQ. FT.)
(GRASS=7,100 SQ. FT.)
(WOODS=5,653 SQ. FT.)

PROPOSED DRAINAGE AREA 'DA2A'
AREA=14,063 SQ. FT.
(IMPERVIOUS=14,063 SQ. FT.)

PROPOSED DRAINAGE AREA 'DA1B'
AREA=13,828 SQ. FT.
(IMPERVIOUS=2,295 SQ. FT.)
(GRASS=8,726 SQ. FT.)
(WOODS=2,607 SQ. FT.)

PROPOSED DRAINAGE AREA 'DA2B'
AREA=12,754 SQ. FT.
(GRASS=11,225 SQ. FT.)
(WOODS=1,529 SQ. FT.)

PROPOSED DRAINAGE AREA 'DA1A'
AREA=59,528 SQ. FT.
(IMPERVIOUS=6,289 SQ. FT.)
(GRASS=29,304 SQ. FT.)
(WOODS=23,935 SQ. FT.)

Tc FLOW PATH

POWDER FOREST DRIVE

HOPMEADOW STREET
(CT ROUTE 10)

FARMINGTON CANAL HERITAGE TRAIL